

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION

FORM CP-1

Rev. 03/92

130 S. Market, Room 2078
Wichita, Kansas 67202

WELL PLUGGING APPLICATION FORM

(PLEASE TYPE FORM and File ONE Copy)

API # 15-007-213080000 (Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate spud or completion date.

WELL OPERATOR Coral Coast Petroleum, L.C. KCC LICENSE # 31691 ^{5/97}
(owner/company name) (operator's)

ADDRESS: 100 N. Main, Suite #505 CITY: Wichita

STATE: Kansas ZIP CODE: 67202 CONTACT PHONE: (316) 269-1233

LEASE: Scoby WELL#: 1 Section 20 Township 32 Range 6w

825' FNL & 445' FEL from NE corner SPOT LOCATION/QQQQ COUNTY: Harper

825 FEET (in exact footage) FROM S / (N) (circle one) LINE OF SECTION (NOT Lease Line)

445 FEET (in exact footage) FROM (E) / W (circle one) LINE OF SECTION (NOT Lease Line)

Check One: Oil Well _____ Gas Well _____ D&A XX SWD/ENHR WELL _____ Docket # _____

CONDUCTOR CASING SIZE None SET AT _____ CEMENTED WITH _____ SACKS

SURFACE CASING SIZE 8-5/8" SET AT 216' CEMENTED WITH 160 SACKS

PRODUCTION CASING SIZE None SET AT _____ CEMENTED WITH _____ SACKS

LIST (ALL) PERFORATIONS and BRIDGEPLUG SETS:

ELEVATION 1430 G.L. 1439 K.B. T.D. 4900 P.B.T.D. _____ Anhydrite Depth _____

(Stone Corral Formation)

CONDITION OF WELL: GOOD _____ POOR _____ CASING LEAK _____ JUNK IN HOLE _____

PROPOSED METHOD OF PLUGGING:

Heavy mud to 1175' then 35 sacks, heavy mud to 800' then 35 sacks, heavy mud to 270' then 35 sacks, heavy mud to 60' then 25 sacks. Using 60/40 Poz with 4% Gel. Plug rathole with 10 sacks.

(If additional space is needed attach separate page)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? Yes (YES,NO) IS ACO-1 FILED? ? (YES,NO)

If not explain why? _____

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Name: Vaughn Thompson/Steve E. McClain Phone#: (316) 672-9508

Address: P.O. Box 1006 City: Pratt State: Kansas

PLUGGING CONTRACTOR: Sterling Drilling Company KCC LICENSE #: 5142 ^{6/97}

(company name) (contractor's)

Address: P.O. Box 1006 City: Pratt State: Kansas Zip 67124

PROPOSED DATE AND HOUR OF PLUGGING (If Known?) Plugged well at 3pm on July 11, 1996

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY: Operator X Agent _____

DATE: 08/14/96 AUTHORIZED OPERATOR OR AGENT: _____

(signature) Steve E. McClain, Agent for Operator

2

Sterling Drilling Company, Rig #4

Box 1006, Pratt, Kansas 67124-1006

Office Phone (316) 672-9508, Fax 672-9509

SAMPLE LOG

API# 15-077-21,3080000

#1 Scoby

LOCATION: 825' FNL & 445' FEL from NE S Section 20 T 32S R 6W
Harper County, Kansas

OWNER: Coral Coast Petroleum, L.C.

COMMENCED: 01-Jul-96

CONTRACTOR: Sterling Drilling Company, Rig #4

COMPLETED: 11-Jul-96

TOTAL DEPTH: DRILLER 4990 FEET

Elevation GL: 1430

LOGGER 4990 FEET

Elevation KB: 1439

LOG

0 -	221 FEET	Top Soil and Redbed (No water sands)
221 -	1585 FEET	Shale
1585 -	4850 FEET	Lime/Shale/Dolomite
4850 -	4990 FEET	Sandstone and Shales

CASING RECORDS

Spud @ 12:30 pm on 7-1-96. Drilled 12 1/4" hole to 221'. Ran 7 joints of Used 24# 8-5/8" surface casing 204.23' set at 216'KB. Cemented with 160 sacks 60/40 Poz, 2% Gel, 3% CC. Plug down at 6:15 pm on 7-1-96 by Allied. Good returns. Ticket # 4036.

Plugged well with 35 sacks at 1175', 35 sacks at 800', 35 sacks at 270', 25 sacks at 60' with 10 sacks in the rathole. Using 60/40 Poz with 4% Gel. Received plugging orders at 2:30pm on 7-8-96 from Gerold Clark - State Plugger. Started plugging well at 1:00 pm and completed plugging at 3:00pm on 7-11-96 by Allied Ticket # 3976.

DEVIATION SURVEYS

1/2	Degrees	221 FEET
2-1/2	Degrees	3548 FEET
1	Degrees	3987 FEET
3/4	Degrees	4460 FEET



Kansas Corporation Commission

Bill Graves, Governor Timothy E. McKee, Chair Susan M. Seltsam, Commissioner John Wine, Commissioner
Judith McConnell, Executive Director David J. Heinemann, General Counsel

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

August 29, 1996

Coral Coast Petroleum L C
100 N Main Suite 505
Wichita KS 67202

Scoby #1
API #15-007-21,308
825 FNL 445 FEL
Sec. 20-32S-06W
Harper County -

Dear Vaughn Thompson/Steve E. McClain,

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.

Please contact the district office for approval of your proposed plugging method at least at five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

Sincerely,

David P. Williams
Production Supervisor

District: #2
130 S. Market Room 2125
Wichita KS 67202-3208
(316) 337-6231