

*rc*  
KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
JAN 8 1966  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Operator's Full Name Amerada Petroleum Corporation

Complete Address: Box 197, Great Bend, Kansas

Lease Name William Steward Well No. # 1

Location C NE NW Sec. 31 Twp. 33 Rge. 6 (E) (W) W

County Harper Total Depth 5010'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: \_\_\_\_\_

Plugging Contractor: Leben Drilling, Inc.

Address: 815 Wichita Plaza, Wichita, Kansas License No. \_\_\_\_\_

Operation Completed: Hour 6:00PM Day 29th Month Dec. Year 1965

The Above well was plugged as follows:

256' of 8 5/8" surface pipe, cement circulated with 200 sacks. Hole  
was filled with drilling mud to 250', 1st cementing plug, bridged solid  
with dry cement and hulls on fluid at 250', and cemented with 35 sacks.  
Hole was filled with drilling mud to 40', 2nd cementing plug, bridged  
solid with dry cement and hulls on fluid at 40', and cemented with 10  
sacks to the base of the cellar. Rat hole bridge~~d~~ and cement~~e~~d with  
2 sacks.

This cementing was done by Halliburton Cementing Company

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Aubie Elving  
Well Plugging Supervisor

DATE 1/4/66  
INV. NO 2539-W