

15-077-2079-0000



Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

RECEIVED
STATE CORPORATION COMMISSION
APR 7 1975
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Min-Tex Oil Corp

Complete Address 503 Mayo Bldg Tulsa, OK

Lease Name Steward Well No. 1

Location C SW/NW Sec. 31 Twp. 33 Rge. 6 (E) (W) W

County Harper Total Depth 4982 2

Abandoned Oil Well _____ Gas Well X Input Well _____ SWD Well _____ D & A _____

Other well as hereafter indicated _____

Plugging Contractor Southwest Casing Pulling Co Inc

Address Box 364 Great Bend, KS License No. 399

Operation Completed: Hour 4:00 PM Day 3 Month 4 Year 1975

The above well was plugged as follows:

223 ft 8 5/8 surface cemented with 126 sacks. 4626 ft 4 1/2 long string
cemented with 100 sacks. Plug back 4592 ft. Top perf. 4499 ft,

Pump 50 sacks cement to 4200 ft. Pulled 3450 ft 4 1/2. Set 10 ft rock
bridge at 480 ft. Fill hole with 8 yds redimix to surface.

I hereby certify that the above well was plugged as herein stated.

Signed: [Signature]
Well Plugging Supervisor

INVOICED

DATE 4/9/75

INV. NO. 1123-W