

1052346

TO: STATE CORPORATION COMMISSION

API NUMBER 15-057-20,554 0000
130'W W/2 E/2 NW SEC. 24, T 29 S, R 22 W

CONSERVATION DIVISION - PLUGGING SECTION 1320 FEET FROM NORTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 1520 FEET FROM WEST SECTION LINE

WICHITA, KANSAS 67202 LEASE NAME MCCAUSTLAND WELL # 1-24

TECHNICIAN'S PLUGGING REPORT 10-24 COUNTY FORD 178.75

OPERATOR LICENSE # 32521 WELL TOTAL DEPTH 5500 FEET

OPERATOR: CORONADO PETROLEUM CORPORATION PRODUCTION CSG: SIZE @ ' WITH SX

NAME AND 105 N HUDSON, SUITE 800 SURFACE CASING: SIZE 8 5/8" @ 676 ' WITH SX

ADDRESS OKLAHOMA CITY, OK 73102 CONDUCTOR CSG : SIZE 20" @ 42'

ABANDONED OIL WELL GAS WELL INPUT WELL SWD WELL D/A X

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR ALLEN DRILLING COMPANY LICENSE NUMBER 5418

ADDRESS PO BOX 1389 GREAT BEND, KS 67530

COMPANY TO PLUG AT: HOUR: 3:00 PM DAY: 24 MONTH: 10 YEAR: 1999

PLUGGING PROPOSAL RECEIVED FROM RICHARD STEVENSON

(COMPANY NAME) ALLEN DRILLING COMPANY (PHONE) 316-793-5681

WERE:

1ST PLUG AT 1450' WITH 50 SX CEMENT. 2ND PLUG AT 700' WITH 50 SX CEMENT.

3RD PLUG AT 40' WITH 10 SX CEMENT. 4TH PLUG TO CIRCULATE RATHOLE WITH 15 SX CEMENT.

5TH PLUG TO CIRCULATE MOUSE HOLE WITH 10 SX CEMENT.

 PLUGGING PROPOSAL RECEIVED BY RICHARD LACEY

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL PART NONE X

OPERATIONS COMPLETED: HOUR: 6:00 PM DAY: 24 MONTH: 10 YEAR: 1999

ACTUAL PLUGGING REPORT LOAD HOLE WITH HEAVY MUD SPOT PLUGS THRU DRILL PIPE

1ST PLUG AT 1450' WITH 50 SX CEMENT. 2ND PLUG AT 700' WITH 50 SX CEMENT.

3RD PLUG AT 40' WITH 10 SX CEMENT. 4TH PLUG TO CIRCULATE RAT HOLE WITH 15 SX CEMENT.

5TH PLUG TO CIRCULATE MOUSE HOLE WITH 10 SX CEMENT.

RECEIVED
STATE CORPORATION COMMISSION

REMARKS: USED 60/40 POZMIX 6% GEL BY ALLIED.

NOV 11-01-99

INVOICED

IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.

I (DID NOT) OBSERVE THIS PLUGGING.

DATE 10/3

SIGNED Richard W. Lacey

INV. NO. 60902

(TECHNICIAN) FORM CP-2/3