

1080328

TO: STATE CORPORATION COMMISSION 70'E 60'S W/2 W/2 SE/4 SEC. 24, T 29 S, R 22 W API NUMBER 15-057-20,555 0000

CONSERVATION DIVISION - PLUGGING SECTION 1260 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 1580 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202

TECHNICIAN'S PLUGGING REPORT

8/15

LEASE NAME DAVIS WELL # 1-24

COUNTY FORD 173.55

OPERATOR LICENSE # 32521 WELL TOTAL DEPTH 5340 FEET

OPERATOR: CORONADO PETROLEUM CORP. PRODUCTION CSG: SIZE @ ' WITH SX

NAME AND 105 N HUDSON, SUITE 800 SURFACE CASING: SIZE 8 5/8" @ 544' WITH SX

ADDRESS OKLAHOMA CITY, OK 73102-4803 CONDUCTOR CSG: SIZE @ '

ABANDONED OIL WELL GAS WELL INPUT WELL SWD WELL D/A X

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR PICKRELL DRILLING CO., INC LICENSE NUMBER 5123

ADDRESS 100 S MAIN, SUITE 505 WICHITA, KS 67202

COMPANY TO PLUG AT: HOUR: 12:00 AM DAY: 15 MONTH: 08 YEAR: 2000

PLUGGING PROPOSAL RECEIVED FROM MIKE KERNS

(COMPANY NAME) PICKRELL DRILLING (PHONE) 316-262-8427

WERE:

1ST PLUG AT 1450' WITH 50 SX CEMENT. 2ND PLUG AT 560' WITH 50 SX CEMENT. 3RD PLUG AT 40' WITH 10 SX CEMENT. 4TH PLUG TO CIRCULATE RAT HOLE WITH 15 SX CEMENT. 5TH PLUG TO CIRCULATE MOUSE HOLE WITH 10 SX CEMENT.

PLUGGING PROPOSAL RECEIVED BY KEVIN STRUBE

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL PART NONE X

OPERATIONS COMPLETED: HOUR: 1:45 AM DAY: 15 MONTH: 08 YEAR: 2000

ACTUAL PLUGGING REPORT LOAD HOLE WITH HEAVY MUD SPOT PLUGS THRU DRILL PIPE

1ST PLUG AT 1450' WITH 50 SX CEMENT. 2ND PLUG AT 560' WITH 50 SX CEMENT. 3RD PLUG AT 40' WITH 10 SX CEMENT. 4TH PLUG TO CIRCULATE RAT HOLE WITH 15 SX CEMENT. 5TH PLUG TO CIRCULATE MOUSE HOLE WITH 10 SX CEMENT.

REMARKS: USED 60/40 POZMIX 6% GEL 1/4 FLO SEAL BY ALLIED.

(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (DID NOT) OBSERVE THIS PLUGGING

INVOICED

DATE 8/29/00

INV. NO. 2001060565

SIGNED Kevin D. Shea (TECHNICIAN)

RECEIVED STATE CORPORATION COMMISSION

AUG 28 2000

CONSERVATION DIVISION Wichita, Kansas

Handwritten initials MB