

10-12

2-060033

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - Plugging Section
200 Colorado Derby Building
Wichita, Kansas 67202

API NUMBER: 15-191-20,499 0000

SW SW SW, SECTION 4 TOWNSHIP 32 RANGE 2W

OPERATOR LICENSE # 7234

330 FEET FROM S SECTION LINE

4950 FEET FROM E SECTION LINE

OPERATOR Arrowhead Petroleum of KS, Inc.

NAME & RR #1, Box 293

ADDRESS Wellington, Kansas 67152

LEASE NAME: S.W.C. #1

COUNTY: Sumner 126.97

WELL TOTAL DEPTH: 3907'

CONDUCTOR PIPE: " @ '

SURFACE CASING: 8-5/8" @ 256'

ABANDONED OIL WELL GAS WELL INPUT WELL SLD D&A

OTHER WELL AS HEREINAFTER INDICATED: 5-1/2" @ 3889' DV @ 2000' open hole

PLUGGING CONTRACTOR: Lyons Well Service

ADDRESS: Lyons, KS LICENSE: 30375

COMPANY TO PLUG AT: HOUR: 1:00 DAY: 12 MONTH: 10 YR: 1990

PLUGGING PROPOSAL RECEIVED FROM: Willis Low

COMPANY NAME: Arrowhead Petro of KS PHONE: 316-326-5725

WERE: Sand back to 3857' - cap w/5 sx - shoot & pull to 620'
& 30 sx plug - pull to 300' & circ to surf - top off.

PLUGGING PROPOSAL RECEIVED BY: Merlan Unruh

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL () PART () NONE ()

COMPLETED: HOUR: 6:00 DAY: 12 MONTH: 10 YEAR: 1990

ACTUAL PLUGGING REPORT:

Sanded back to 3857' & capped w/5 sx - shot @ 1590' -
pulled to 670' & spotted 30 sx plug thru 5-1/2" -
pulled to 335' & circ to surf thru 5-1/2" with 120 sx.

REMARKS: United #720

I DID OBSERVE THIS PLUGGING.

x. Dave Wertz
Dave Wertz (AGENT)

RECEIVED
STATE CORPORATION COMMISSION

OCT 31 1990

CONSERVATION DIVISION
Wichita, Kansas

INVOICED

DATE 11-6-90
INV. NO. 29825

FORM CP-2/3
REV. 3/90