

To: 1 3-30  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-007-21,833  
100' E of  
NW SW NW, SEC. 13, T. 32 S, R. 11 W/E

TECHNICIAN'S PLUGGING REPORT  
Operator License # 30128  
Operator: Kenneth S. White  
Name & Address: 200 E. 1st, Suite 210  
Wichita, KS 67202

3630 feet from S section line  
4850 feet from E section line  
Lease Name Hrencher Well # 2  
County Barber 123.22  
Well Total Depth 3810 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 226

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050

Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 1:15 p.m. Day: 30 Month: 3 Year: 1992

Plugging proposal received from Vernon Duntz

(company name) Kelso Casing Pulling, Inc. (phone) 316-938-2943

were: 5 1/2" at 3807' w/100 sx cement, PBSD 3656', Perfs at 3750-53, 3616-20'

1st plug pump 25 sx cement at 3550',

2nd plug pump 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, release

8 5/8" wiper plug and pump 100 sx cement.

Plugging Proposal Received by Richard Lacey  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 2:40 p.m. Day: 30 Month: 3 Year: 1992

ACTUAL PLUGGING REPORT 1st plug pumped down 5 1/2" casing with 25 sx common cement, stopped plug at 3550',

2nd plug pumped down 8 5/8" surface pipe with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 100 sx cement.

Maximum pressure 550 psi and shut in 400 psi.

Remarks: Used 60/40 Pozmix 6% gel by B.J. Services. Recovered 3200' of 5 1/2" casing.  
(if additional description is necessary, use BACK of this form.)

(if possible) observe this plugging.

INVOICE

DATE 4-8-92

INV. NO. 34917

Signed Stephen J. Pfeiffer  
(TECHNICIAN)