

10-2

2-070411

171
L

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - Plugging Section
200 Colorado Derby Building
Wichita, Kansas 67202

API NUMBER: 15-191-21,343 0000

E/2 NE SW, SECTION 18 TOWNSHIP 33 RANGE 3W

OPERATOR LICENSE # 30705 1950 FEET FROM S SECTION LINE
2970 FEET FROM E SECTION LINE

OPERATOR B-Y Operating, Inc.
NAME & 251 N. Water, #12
ADDRESS Wichita, KS 67202

LEASE NAME: Childs #1
COUNTY: Sumner
WELL TOTAL DEPTH: 4508'

46.51

CONDUCTOR PIPE: " @ ' "

SURFACE CASING: 8-5/8" @ 250'

ABANDONED OIL WELL X GAS WELL _____ INPUT WELL _____ SLD _____ D&A _____

OTHER WELL AS HEREINAFTER INDICATED: _____

PLUGGING CONTRACTOR: B & S Well Service
ADDRESS: P. O. Box 837, Winfield, KS 67156 LICENSE: 6013

COMPANY TO PLUG AT: HOUR: 12:00 DAY: 1 MONTH: 10 YR: 1991

PLUGGING PROPOSAL RECEIVED FROM: Bobby
COMPANY NAME: _____ PHONE: 316-221-2030

WERE: Push plug to 2982' - 50' chat & 4 sx - 35 sx @ 950' -
35 sx @ 625' - 300' to surface.

PLUGGING PROPOSAL RECEIVED BY: Steve Van Gieson

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL (X) PART (_____) NONE (_____)

COMPLETED: HOUR: 11:30 DAY: 2 MONTH: 10 YEAR: 1991

ACTUAL PLUGGING REPORT:
Had tubing in the hole to 2982' - pushed plug to
2982' - 50' chat & 4 sx common - shot 4-1/2" csg @
2890' - pulled to 950' - pumped 35 sx - pulled to 625' -
pumped 35 sx - pulled to 300' - pumped to surf.

REMARKS: _____

RECEIVED
KANSAS CORPORATION COMMISSION

I DID OBSERVE THIS PLUGGING.

OCT 29 1991

Jack Luthi
Jack Luthi (AGENT)

CONSERVATION DIVISION
WICHITA, KS
FORM CP-273
REV. 3/90

INVOICED

DATE 11-8-91
INV. NO. 33660

DW