

1010150

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 6879

Operator: Solar Petroleum, Inc.
Name & Address: 1099 18th St. Suite 2900
Denver, CO 80202-1999

API NUMBER 15-101-21,015 -0000
SW/4 NE/4 SE/4, SEC. 36, T 17 S, R 28 W
1650 feet from section line
990 feet from section line

Lease Name Royce Wheatcroft Well # 1

County Lane

Well Total Depth 4700 152.75 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 342

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor H-30, Inc. License Number 5107

Address 251 North Water, Suite 10, Wichita, KS 67202

Company to plug at: Hour: 5:00 pm Day: 4 Month: August Year: 19 84

Plugging proposal received from Roger Wheatcroft

(company name) H-30 (phone) 316-263-2043

were: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 2077' with 50 sx cement

2nd plug at 1240' with 50 sx cement

3rd plug at 375' with 50 sx cement
solid bridge

4th plug hulls - plug at 40' -- cement to surface with 10 sx cement

6th plug to circulate rat hole with 10 sx cement

Plugging Proposal Received by (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 7:30 pm Day: 4 Month: August Year: 1984

ACTUAL PLUGGING REPORT 1st plug at 2077' with 50 sx cement, 2nd plug at 1240' with

50 sx cement, 3rd plug at 375' with 50 sx cement, 4th & 5th plugs - solid bridge - hulls -

plug at 40' -- cement to surface with 10 sx cement, 6th plug to circulate rat hole with

10 sx cement.

RECEIVED
STATE CORPORATION COMMISSION

AUG 10 1984

8-10-84
CONSERVATION DIVISION
Wichita, Kansas

Remarks: Used 60/40 Pozmix 2% gel 3% cc by Allied.

(If additional description is necessary, use BACK of this form)

did not observe this plugging.

INVOICED
DATE 8-14-84

Signed Ken Brasen (TECHNICIAN)

INV. NO. 3091