

To: 1 05 638  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

4-22

API NUMBER 15-101-20,820-0000

620

NW NW SE, SEC. 34, T. 17 S, R. 28 W/4

2310 feet from S section line

2310 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5408

Lease Name A. Boltz Well # 1

Operator: Moble C. Hoover

County Lane

Name & Address NBC Plaza Bldg., Ste. 302

Well Total Depth 4306 139.94 feet

El Dorado, AR 71730

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 319

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereinafter indicated

Plugging Contractor Allied Cementing License Number

Address

Company to plug at: Hour: 11:30 a.m. Day: 22 Month: 4 Year: 19 93

Plugging proposal received from R.D. Rapp

(company name) Moble C. Hoover (phone) 316-793-8186

work: 4 1/2" at 4304' w/300 sx cement, PBD 4260', Perfs at 4053-57, 4238-40', DV tool at 1568' w/400 sx cement

1st plug pump 3 sx hulls and 230 sx cement down 4 1/2" casing,

2nd plug check backside.

Plugging Proposal Received by Steve Durrant (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part  None

Operations Completed: Hour: 12:45 p.m. Day: 22 Month: 4 Year: 1993

ACTUAL PLUGGING REPORT 1st plug pumped down 4 1/2" with 300 lbs. hulls and 230 sx cement.

Maximum pressure 1000 psi and shut in 500 psi.

Pressured 8 5/8" X 5 1/2" annulus to 500#. It did not take any cement.

Remarks: Used 65/35 Pozmix 6% gel by Allied. No casing recovery.

(If additional description is necessary, use BACK of this form)

Observe this plugging.

INVOICED

DATE 4-29-93

37629

Signed Richard W. Lach (TECHNICIAN)

4-26-93  
RECEIVED  
STATE CORPORATION COMMISSION  
RECEIVED  
STATE CORPORATION COMMISSION  
APR 26 1993  
CONSERVATION DIVISION  
WICHITA, KANSAS