

1041324

15-151-21318-0001

TO: STATE CORPORATION COMMISSION 10-29 API NUMBER 15-151-21,318-00-01
150'E NE SW SEC. 4, T 29 S, R 12 W

CONSERVATION DIVISION - PLUGGING SECTION 1980 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 2130 FEET FROM WEST SECTION LINE

WICHITA, KANSAS 67202 LEASE NAME BRUBAKER "A" WELL # 1

TECHNICIAN'S PLUGGING REPORT COUNTY PRATT

OPERATOR LICENSE # 30705 WELL TOTAL DEPTH 4337 140.95 FEET

OPERATOR: YOUNGER ENERGY COMPANY PRODUCTION CSG: SIZE 5 1/2" @ 4330' WITH 150 SX

NAME AND 453 S WEBB, SUITE 100 SURFACE CASING: SIZE 8 5/8" @ 388' WITH 350 SX

ADDRESS WICHITA, KS 67207

ABANDONED OIL WELL GAS WELL INPUT WELL SWD WELL E-27,360 D/A

OTHER WELL AS HEREINAFTER INDICATED _____

PLUGGING CONTRACTOR DS&W WELL SERVICING LICENSE NUMBER 6901

ADDRESS PO BOX 231 CLAFLIN, KS 67525

COMPANY TO PLUG AT: HOUR: 11:30 AM DAY: 29 MONTH: 10 YEAR: 1998

PLUGGING PROPOSAL RECEIVED FROM KENT STRUBE

(COMPANY NAME) DS&W (PHONE) 316-587-3361

WERE: PERFS AT 4260-70

1ST PLUG SAND TO 4200' AND 5 SX CEMENT. 2ND PLUG AT 770' WITH 50 SX CEMENT,

3RD PLUG AT 415' WITH 50 SX CEMENT, 4TH PLUG AT 40' WITH 10 SX CEMENT.

PLUGGING PROPOSAL RECEIVED BY STEVE PFEIFER

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL PART _____ NONE _____

OPERATIONS COMPLETED: HOUR: 12:45 PM DAY: 29 MONTH: 10 YEAR: 1998

ACTUAL PLUGGING REPORT _____

1ST PLUG SAND BACK TO 4200' AND PUT 5 SX CEMENT ON TOP OF SAND BRIDGE THROUGH BAILER.

LOAD HOLE WITH GEL. SPOT PLUGS THROUGH 5 1/2" CASING. 2ND PLUG AT 760' WITH 50 SX CEMENT.

3RD PLUG AT 410' WITH 50 SX CEMENT, 4TH PLUG AT 40' WITH 10 SX CEMENT.

REMARKS: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 2100' OF 5 1/2" CASING.
(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (DID) OBSERVE THIS PLUGGING.

SIGNED Stephen J. Pfeifer
(TECHNICIAN) FORM CP-2/3

RECEIVED
KANSAS
CORP COM
NOV 6 12 39

60287