

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-151-21,318

LEASE NAME Brubaker "A"

WELL NUMBER 1

1980 Ft. from S Section Line

3150 Ft. from E Section Line

SEC. 4 TWP. 29 SRGE. 12 (X) or (W)

COUNTY Pratt

Date Well Completed 9-9-83

Plugging Commenced 10-28-98

Plugging Completed 10-29-98

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Younger Energy Company

ADDRESS 453 S. Webb Rd., Ste 100, Wichita, KS 67207

PHONE# (316) 681-2542 OPERATORS LICENSE NO. 30705

Character of Well Input

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on October 29, 1998 (date)

by Steve Pfeiffer (KCC District Agent's Name).

Is ACO-1 filed? yes If not, is well log attached? _____

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 4337'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

| Formation | Content | From | To | Size | Put In | Pulled out |
|-------------|------------|------|------|--------|--------|------------|
| Mississippi | | 4260 | 4270 | | | |
| | Surface | | | 8-5/8" | 388' | 0 |
| | Production | | | 5-1/2" | 4330' | 2081.55' |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set.
Bottom plug; sanded to 4200', 5 sks of cement. Loaded hole with 10 sks gel.
Allied pumped 50 sks of cement 60/40 6% gel at 760'. Pumped 50 sks at 410'.
Circulated cement to surface with 20 sks, hole stayed full.

Name of Plugging Contractor DS&W Well Servicing Inc. License No. 6901

Address P.O. Box 231, Claflin, KS 67525

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Younger Energy Company

STATE OF Kansas COUNTY OF Sedgwick, ss.

Gary Younger (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed the the same are true and correct, so help me God.

(Signature) [Signature]

(Address) 453 S. Webb Rd., Suite 100
Wichita, KS 67207

SUBSCRIBED AND SWORN TO before me this 25th day of NOVEMBER, 19 98

Deane Leebstock
Notary Public



Commission Expires: MARCH 29, 2002