



JOHN ANDERSON, Jr. Governor
RICHARD C. BYRD Chairman
ALVIN F. GRAUERHOLZ Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

OCT 26 1964
10-26-64
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Dear Sir:

Mr. Sullivan of Sierra Petroleum Company has this

date requested permission to plug the following described well:

Mr. Sullivan guarantees payment of the plugging fee.

Operator's full Name: Dorset Company

Complete Address: 610 National Bank Building, Tulsa, OKLAHOMA

Lease Name: Metz A Well No. #1

Location: C-NE-SW Sec. 10 Twp. 34 Rge. 6 (E)(W) W

County Harper Total Depth 4531 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Sullivan was instructed to plug the well as follows:

252 feet of 8 5/8 inch surface pipe circulated with 225 sacks cement. Heavy
drilling mud to 180 feet, 1st cementing plug; 1/4 sack Hulls cemented with
25 sacks, hole filled to 40 feet with heavy drill mud; 2nd cementing plug and
10 sacks cement. Rat hole bridged with 2 sacks cement.

Very truly yours,

Conservation Division Agent