



# State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market

WICHITA, KANSAS 67202

RECEIVED  
STATE CORPORATION COMMISSION

MAY 24 1972

CONSERVATION DIVISION  
Wichita, Kansas

### VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Abercrombie of Patrick has this

date requested permission to plug the following described well:

Mr. Abercrombie guarantees payment of the plugging fee.

Operator's full Name: Patrick Petroleum Corp.

Complete Address: 220 W. Douglas, Wichita, Kansas

Lease Name: Knoefler Well No. 1

Location: C NW SE Sec. 33 Twp. 21 Rge. 25 XX (E) (W)

County: Hodgeman Total Depth 4705' Oil Well

Gas Well  Input Well  SWD Well  D & A  Lost Hole

Mr. Abercrombie was instructed to plug the well as follows:


8 5/8" to 485' circulated w/ cement. Mud 4705' to 850'

Spot 80 sacks cement 850' to 550' Mud 550' to 485'

Spot 30 sacks cement 485' to 385' Mud 385' to 45'

Plug, Hulls & 15 sacks cement 45' to 0'.

Very truly yours,

  
Conservation Division Agent