



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217

RECEIVED
STATE CORPORATION COMMISSION

JUN 21 1974

CONSERVATION DIVISION
Wichita, Kansas

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Lyons of Atlantic Drlg Co has this

date requested permission to plug the following described well:

Mr. Lyons guarantees payment of the plugging fee.

Operator's full Name: Ascot Oils Inc

Complete Address: 3545 N.W. 58 Suite 560 Oklahoma City, OK

Lease Name: Hest-Thompson Well No. 1

Location: C NW Sec. 26 Twp. 34S Rge. 18 (E)(W) W

County: Gemanche Total Depth 6305 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Lyons was instructed to plug the well as follows:

234 ft 8 5/8 surface cemented with 250 sacks. Pump 40 sacks

cement to 400 ft. 2nd plug at 200 ft, 25 sacks cement.

Mud to 40 ft, plug, 1/2 sack hulls, 15 sacks cement to

surface. 2 sacks cement in rat hole. 2 sacks in mouse hole.

Pumped by Allied Cementing Co Great Bend, KS

Very truly yours,

A Russell Bickert
Conservation Division Agent