

State of Kansas



15-077-00286-9900 FORM - CP-2

JOHN ANDERSON, Jr. Governor
RICHARD C. BYRD Chairman
ALVIN F. GRAUERHOLZ Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
CHARLES C. McCARTER Gen. Counsel

State Corporation Commission
CONSERVATION DIVISION
(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

NOV 18 1963
11-18-63
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Dear Sir:

Mr. Bill Wood of Texaco Inc. has this

date requested permission to plug the following described well:

Mr. Wood guarantees payment of the plugging fee.

Operator's full Name: Texaco Inc.

Complete Address: 614 Bitting Bldg., Wichita, Kansas

Lease Name: Hunter Well No. # 1

Location: SE SW Sec. 18 Twp. 32 Rge. 6 (E) (W) W

County Harper Total Depth 4911 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Wood was instructed to plug the well as follows:

355' of 8 5/8" surface pipe, cemented with 200 sacks.
Fill hole with drilling mud to 300', 1st cementing plug,
1/2 sack hulls, cement with 25 sacks. Fill hole with drill-
ing mud to 40', 2nd cementing plug, 1/2 sack hulls, cement
with 10 sacks to base cellar. Bridge and cement rat hole
with 2 sacks.

Very truly yours,

Archie Elving
Conservation Division Agent