



15-007-20360-0000

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

WICHITA, KANSAS

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

New Address
245 North Water
Wichita, Kansas 67202
RECEIVED
STATE CORPORATION COMMISSION

FEB 25 1976

CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Cameron of H-30 Drlg Co has this

date requested permission to plug the following described well:

Mr. Cameron guarantees payment of the plugging fee.

Operator's full Name: National Oil Co

Complete Address: Suite 550 OW Garvey Bldg Wichita, KS

Lease Name: Shaft Well No. 1

Location: NW/NW/NE Sec. 19 Twp. 31s Rge. 14 (E)(W) W

County: Barber Total Depth 4704 Oil Well

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Cameron was instructed to plug the well as follows:

116 ft 10 3/4 surface cemented with 100sacks.

848 ft 8 5/8 surface cemented with 450 sacks. Pump plug,

35 sacks cement to 300 ft. Mud to 40 ft. plug, 1/2 sack

hulls, 15 sacks cement to surface. 2 sacks cement in

rat hole.

Pumped by Halliburton Cementing, Great Bend, KS

Very truly yours,

Russell Bilbrey
Conservation Division Agent