

7-27

2-050253

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - Plugging Section
130 S. Market, Room 2078
Wichita, Kansas 67202

API NUMBER: 15-191-20,630 OOO

SE SE SE, SECTION 22 TOWNSHIP 33 RANGE 3W

OPERATOR LICENSE # 6765 330 FEET FROM S SECTION LINE
330 FEET FROM E SECTION LINE

OPERATOR DEAN ALLISON OIL COMPANY
NAME & ADDRESS 507 LANDMARK SQUARE
212 N. MARKET
WICHITA KS 67202

LEASE NAME: ROHRER #1
COUNTY: SUMNER
WELL TOTAL DEPTH: 4481' 145.63

PIPE: 4-1/2" @ 3596'
SURFACE CASING: 8-5/8" @ 253'

ABANDONED OIL WELL GAS WELL INPUT WELL SMD D&A

OTHER WELL AS HEREINAFTER INDICATED: _____

PLUGGING CONTRACTOR: KELSO CASING PULLING INC
ADDRESS: PO BOX 347, CHASE KS 67524-0347 LICENSE: 6050

COMPANY TO PLUG AT: HOUR: 10:00 DAY: 27 MONTH: 7 YR: 1994

PLUGGING PROPOSAL RECEIVED FROM: DIST 2
COMPANY NAME: ALLIED CEMENTING PHONE: 316-886-5926

WERE: SAND BACK AND SPOT 4 SX CMT @ 3450' - SHOOT 4-1/2" CSG
@ 2800' - PULL CSG TO 650' & SPOT 35 SX CMT - PULL CSG
TO 350' & CIRC CMT TO SURF - PULL CSG OUT OF HOLE &
TOP OFF WITH CEMENT

PLUGGING PROPOSAL RECEIVED BY: VERNON DUNTZ

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL () PART () NONE ()


COMPLETED: HOUR: 13:00 DAY: 27 MONTH: 7 YEAR: 1994

ACTUAL PLUGGING REPORT:
SANDED BACK & SPOTTED 4 SX CMT @ 3450' - SHOT 4-1/2"
CSG @ 2800' - PULLED CSG TO 650' & SPOTTED 35 SX -
PULLED CSG TO 350' & CIRC CMT TO SURF - PULLED CSG OUT
OF HOLE & TOPPED OFF W/CMT

REMARKS: ALLIED #4744 165 SX CMT 60/40 POZ 4% GEI

INVOICED

DATE 9-8-94
INV. NO. 41140


Jerry Clark
(AGENT)

RECEIVED
KANSAS CORPORATION COMMISSION

SEP 06 1994

CONSERVATION DIVISION
WICHITA, KS
CP-2/3
REV. 3/90