

1060156

To: STATE CORPORATION COMMISSION
 CONSERVATION DIVISION - PLUGGING SECTION SE NW SW, SEC. 33, T 17 S, R 28 W/4
 200 COLORADO DERBY BUILDING
 WICHITA, KANSAS 67202

API NUMBER 15-101-20,907-000

TECHNICIAN'S PLUGGING REPORT

Operator License # 6735

1650 feet from N/S section line

990 feet from W/E section line

Operator: Southwestern Energy Prod. Co.

Lease Name Bretz Well # 1

Name &

County Lane

Address 1001 N.W. 63, Suite 200

Well Total Depth 4662 151.51 feet

Oklahoma City, OK 73116

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 273

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor DaMac Drilling, Inc. License Number 6333

Address Box 1164, Great Bend, KS 67530

Company to plug at: Hour: 9:00 am Day: 11 Month: February Year: 19 84

Plugging proposal received from John Crowe

(company name) DaMac Drilling (phone) 316-792-1353

were: to fill hole with heavy mud and spot cement through drill pipe.

1st plug at 2100' with 50 sx cement

2nd plug at 1260' with 50 sx cement

3rd plug at 320' with 50 sx cement

solid bridge

4th plug hulls - plug at 40' -- cement to surface with 10 sx cement

6th plug to circulate rathole with 15 s x cement, 7th plug to circulate mousehole with 10 sx cement

Plugging Proposal Received by

Paul A. Luthi
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 12:50 Day: 10 Month: February Year: 19 84

ACTUAL PLUGGING REPORT 1st plug at 2100' with 50 sx cement, 2nd plug at 1260' with 50

sx cement. 3rd plug at 320' with 50 sx cement. 4th & 5th plugs solid bridge - hulls - plug

at 40' -- cement to surface with 10 sx cement, 6th plug to circulate rathole with 15 sx

cement and 7th plug to circulate mousehole with 10 sx cement.

Remarks: Use 60/40 Pozmix with 2% gel 3% cc. by Allied

(additional description is necessary, use BACK of this form.)

INVOICED

I (did / did not) observe this plugging.

DATE 2-22-84

INV. NO. 0310

Signed

Paul A. Luthi
(TECHNICIAN)

RECEIVED
 STATE CORPORATION COMMISSION
 FEB 15 1984
 CONSERVATION DIVISION
 Wichita, Kansas