

To: 1 060089
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

8-24 339
API NUMBER 15- 171-20,434-0000
C NW SE, SEC. 26, T 17 S, R 32 W/4E
1980 feet from S section line
1980 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 3842
Operator: Larson Operating Company
Name & Address: P.O. Box 553
Great Bend, KS 67530

Lease Name Brookover Well # 2
County Scott 152.42
Well Total Depth 4690 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 257

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X
Other well as hereinafter indicated _____

Plugging Contractor Emphasis Oil Operations License Number 8241
Address P.O. Box 819, Russell, KS 67665

Company to plug at: Hour: 7 a.m. Day: 24 Month: 8 Year: 19 91

Plugging proposal received from Bill Owens
(company name) Emphasis Oil Operations (phone) 913-483-3518

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 2301-21'
1st plug at 2330' with 50 sx cement, 2nd plug at 1500' with 80 sx cement,
3rd plug at 750' with 50 sx cement, 4th plug at 290' with 50 sx cement,
5th plug at 40' with 10 sx cement, 6th plug to circulate rathole with 15 sx cement,
7th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Case Morris (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 10 a.m. Day: 24 Month: 8 Year: 19 91

ACTUAL PLUGGING REPORT 1st plug at 2330' with 50 sx cement,

2nd plug at 1500' with 80 sx cement,

3rd plug at 750' with 50 sx cement,

4th plug at 290' with 50 sx cement,

5th plug at 40' with 10 sx cement, 6th plug to circulate rathole with 15 sx cement,
7th plug to circulate mousehole with 10 sx cement.

RECEIVED
STATE CORPORATION COMMISSION
AUG 30 1991
8-30-91
CONSERVATION DIVISION
Wichita, Kansas

Remarks: Used 60/40 Pozmix 6% gel 1/4# floseal by HOWCO.
(if additional description is necessary, use BACK of this form.)

INVOICED

DATE 9-13-91
INV. NO. 33109

Signed Case Morris (TECHNICIAN)