

1031471

11-2

To: STATE CORPORATION COMMISSION
Wichita, State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

API NUMBER 15- 171-20,519-0000
100' S & 100' E of
NW SE SE, SEC. 26, T 17 S, R 32 W X
890 feet from S section line
890 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License / 4243
Operator: Cross Bar Petroleum, Inc.
Name & Address: 7570 W. 21st St., Bldg. 1014, Ste. B
Wichita, KS 67205

Lease Name Brookover Well # 1-26
County Scott 154.38
Well Total Depth 4750 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 340

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Cheyenne Drilling, Inc. License Number 5382

Address P.O. Box 916, Garden City, KS 67846

Company to plug at: Hour: 3 p.m. Day: 2 Month: 11 Year: 19 97

Plugging proposal received from Duane Bell

(company name) Cheyenne Drilling, Inc. (phone) 316-277-2062

was: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 2302-30'

1st plug at 2330' with 50 sx cement, 2nd plug at 1625' with 80 sx cement,

3rd plug at 900' with 40 sx cement, 4th plug at 360' with 40 sx cement,

5th plug at 40-0' with 10 sx cement, 6th plug to circulate rathole with 15 sx cement,

7th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Steve Durrant (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 11:30 p.m. Day: 2 Month: 11 Year: 19 97

ACTUAL PLUGGING REPORT 1st plug at 2330' with 50 sx cement,

2nd plug at 1625' with 80 sx cement, 3rd plug at 900' with 40 sx cement,

4th plug at 360' with 40 sx cement,

5th plug at 40-0' with 10 sx cement,

6th plug to circulate rathole with 15 sx cement,

7th plug to circulate mousehole with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel 1/4# floseal by Allied.

INVOICED (Additional description is necessary, use BACK of this form.)

I (XXXX/ did not) observe this plugging.

DATE 11-14-97

Signed Steve Durrant (TECHNICIAN)

INV. NO. 49495