

To: 1 05 639  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

4-22 API NUMBER 15- 101-20,729-0000 612

SW SE SW, SEC. 34, T. 17 S, R. 28 W/E

330 feet from S section line

3630 feet from E section line

Lease Name Howard Cartmill Well # 1

County Lane 138.22

Well Total Depth 4253 feet

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 277

TECHNICIAN'S PLUGGING REPORT

Operator License # 5408

Operator: Moble C. Hoover

Name & Address NBC Plaza Bldg., Ste. 302

El Dorado, AR 71730

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Allied Cementing License Number \_\_\_\_\_

Address \_\_\_\_\_

Company to plug at: Hour: 10:15 a.m. Day: 22 Month: 4 Year: 19 93

Plugging proposal received from R.D. Rapp

(company name) Moble C. Hoover (phone) 316-793-8186

work: 5 1/2" at 4251' w/200 sx cement, Open hole 4251-53', DV at 1337' w/400 sx cement

1st plug pump 3 sx hulls and 330 sx cement down 5 1/2".

2nd plug pump 1 sx hulls and 50 sx cement down annulus.

Plugging Proposal Received by Steve Durrant  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 11:30 a.m. Day: 22 Month: 4 Year: 19 93

ACTUAL PLUGGING REPORT 1st plug pumped down 5 1/2" with 300 lbs. hulls and 330 sx cement.

Maximum pressure 1000 psi and shut in 100 psi.

2nd plug pumped down 8 5/8" X 5 1/2" annulus with 100 lbs. hulls and 50 sx cement.

Maximum pressure 500 psi and shut in 100 psi.

Remarks: Used 65/35 Pozmix 6% gel by Allied. No casing recovery.

RECEIVED  
STATE CORPORATION COMMISSION

**INVOICED**

(If additional description is necessary, use BACK of this form)

DATE 4-29-93

TEL. NO. 376 30

Signed Richard W. Lundy  
(TECHNICIAN)

APR 26 1993  
4-26-93  
CONSERVATION DIVISION  
Wichita, Kansas