

15-145-20144-0000

Form CP-3  
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
APR 28 1970  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name Pickrell Drilling Company

Complete Address 705 Fourth National Bank Building Wichita, Kansas 67202

Lease Name Schadel "A" Well No. 2

Location NW SW Sec. 6 Twp. 20 Rge. (E) (W) 20

County Pawnee Total Depth 4392

Abandoned Oil Well IX Gas Well        Input Well        SWD Well        D & A       

Other well as hereafter indicated       

Plugging Contractor Russ Casing Pulling Co.

Address Box 1082 Great Bend, Kansas License No. 623

Operation Completed: Hour 3:15 P Day 25 Month 4 Year 1970

The above well was plugged as follows:

Total Depth 4392' 8 5/8 csg set at 261' cwc

5 1/2 csg set at 4385' cw 125 sk cmt.

Filled 5 1/2 csg W/sd (4300-4392) Dumped 5 sk cmt W/dump bailer. (4260-4300)

Cutoff and recovered 3112' of 5 1/2 csg.

Pumped thru 8 5/8 plug container with 20 sk gel W/3 sk hulls, plug and 130 sk

50-50 poz cmt W/6% total gel.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo F. Muesel  
Well Plugging Supervisor

DATE 4/28/70

INV. NO. 1806-4