

Form CP-3
Rev. 6-26-62

~~NO~~ KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

AUG 13 1964

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Ferguson Oil Company

Complete Address: 522 Union Center, Wichita, Kansas

Lease Name Herd Well No. # 1

Location C NE SW Sec. 34 Twp. 32 Rge. 19 (E) (W)W

County Comanche Total Depth 5348

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: D & M Drilling Co., Inc.

Address: 809 Union Center, Wichita, Kansas License No.

Operation Completed: Hour 1:00AM Day 11th Month August Year 1964

The Above well was plugged as follows:

409' of 13 3/8" surface pipe, cement circulated with 450 sacks. Hole
was filled with drilling mud to 300', 1st cementing plug, bridged solid
with hulls, on fluid at 300', and cemented with 40 sacks. Hole was fill-
ed with drilling mud to 40', 2nd cementing plug, bridged solid with hulls
on fluid at 40', and cemented with 20 sacks to the base of the cellar.
Rat and mouse hole bridged and cemented with 4 sacks.

I hereby certify that the above well was plugged as herein stated.

INVOICED
DATE 8/13/64
INV. NO. 9646-4

Signed: Archie Elving
Well Plugging Supervisor