

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT REPORT

FORM CP-3
RECEIVED 8-82
STATE CORPORATION COMMISSION
AUG 04 1982
CONSERVATION DIVISION
Wichita, Kansas
0000 ✓ P

API Number 15-023-20,421

200 Colorado Derby Building
Wichita, KS 67202

Operator's Full Name Tutthill & Barby

Complete Address 300 Fish Amarillo Texas 79101

Lease Name Gillet Well No. 1-34

Location C-NW Sec. 34 Twp. 32 Rge. 19 (East)(West)

County Comanche Total Depth 5230

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated _____

Plugging Contractor Reeves & Wilson, Inc.

Address Woodward Okla License No. 530

Operation Completed: Hour: 1:00 PM Day: 28 Month: July Year: 1982

Plugging Operations attended by Agent?: All Part None

The above well was plugged as follows:

They had 5230' of 4 1/2" production pipe set. They perforated the 4 1/2" from 5192' to 5210'. 1st plug is a cast iron plug at 5050' with 1 sbk of cement on it. 2nd plug at 850' with 40 sbk of cement. 3rd plug 40' to 0' on solid bridge with 10 sbk of cement. They recovered 4038' of 4 1/2" pipe. The plugging was accomplished by Reeves & Wilson Inc.

Amount of Surface Casing: 797' of 8 5/8"

I hereby certify that the above plugging instructions were given as herein stated.

Signed: Paul A. Luthis
Conservation Division Agent

I hereby state that I was not present while the above well was being plugged, however, to the best of my knowledge and belief it was plugged as herein stated. A full account for my not being present is as follows:

I had other work to do at the time this well was plugging

Signed: Paul A. Luthis
Conservation Division Agent

INVOICED

8-9-82
833-W