

KANSAS

FORM CP-3  
Rev. 5-5-81

STATE CORPORATION COMMISSION

RECEIVED  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT REPORT

SEP 17 1981

API Number 15-0-33-20450 0000 <sup>Wichita, Kansas</sup>

200 Colorado Derby Bldg.  
Wichita, KS 67202

CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name K.R.M. Petroleum Corporation  
Complete Address 820 Guaranty Bank Bldg 817, 17th St. Denver, Colo. 80202  
Lease Name Kerstetter Well No. 1-33

Location CNW-NE Sec. 33 Twp. 32 Rge. 19W (East) (West)  
County Cranache Total Depth 5220'

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated \_\_\_\_\_

Plugging Contractor Kirkman Drilling Co.  
Address 453-S Webb Rd. Box 18611 <sup>Wichita</sup> ~~Kans~~ 67207 License No. \_\_\_\_\_

Operation Completed: Hour: 1:45 AM Day: 13 Month: September Year: 19 81

Plugging Operations attended by Agent? All  Part  None

The above well was plugged as follows:

There is 676' of 8 5/8" surface casing cement circulated with 400 sks of cement. They had hole full of heavy mud. 1st Plug pushed rubber plug to 650' and put 40 sks of cement on top of rubber plug. 2nd Plug with hole full of heavy mud put 1 sk of hulls at 40' to make solid bridge and put 10 sks of cement on top of bridge cement from 40' to 0; then 10 sks in rat hole + 10 sks in mouse hole. Plugging accomplished by Helibenton Co.

**INVOICED**  
I hereby certify that the above well was plugged as herein stated.

DATE 10-29-81

Signed: Paul Luthi  
Conservation Division Agent

INV. NO. ~~8142W~~ 8142W