

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-101-20498-0001
NE SE SW, Sec. 3, T 19 S, R 29 W
_____ feet from N/S section line
_____ feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5198

Lease Name Mcwhirter Well # 1

Operator: A Scott Ritchie
Name & Address Suite 950,
125 N. Market
Wichita KS, 67202

County Lane
Well Total Depth 4675 feet 151.94
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 376

Abandoned Oil Well X Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Box 126 Chase KS 67524

Company to plug at: Hour: 9:30am Day: 4 Month: November Year: 1983

VERBAL PLUGGING ORDERS GIVEN TO Mike Gomez

(company name) Kelso Casing Pulling (phone) _____

were: 1st plug off bottom with sand to 4260' +
dump 45x cement, Then squeeze 8 5/8" surface
pipe with 35xhulls - 10gel - 70sxcement - 10gel
1 hull - 1 8 5/8 wiper plug - 120 sxcement using
60/40 pezmix 2%ogel 3%cc

Signed Richard W. Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part _____ None _____

Operations Completed: Hour: 10:15 am Day: 4 Month: November Year: 1983

ACTUAL PLUGGING REPORT Plugged as proposed in above paragraph
Recovered 1350' of 4 1/2" production pipe
Maximum pump pressure 700 psi
Shut in pressure 200 psi
Allied pumped the cement

Remarks: _____

I hereby certify that the above plugging instructions were given as herein stated and that I (did / ~~did not~~) observe this plugging.

INVOICED
DATE 11-21-83
INV. NO. 2014-W

RECEIVED
STATE CORPORATION COMMISSION
NOV 9 1983
11-9-83
CONSERVATION DIVISION
Wichita, Kansas

Signed Richard W. Lacey
(TECHNICIAN)