

1 050556

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 101-21,178-0000

NW SW SE, SEC. 3, T 19 S, R 29 W/R

990 feet from S section line

2310 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5020 & 6390

Lease Name Snyders Well # 1-3

Operator: Rine Exploration & McDonald-Wallace County Lane 150.58

Name & Address 300 W. Douglas, Suite 645 Well Total Depth 4633 (Mississippi) feet

Wichita, KS 67202

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 396' ✓

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SMD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Blue Goose Drilling, Inc. License Number 5104

Address Box 1413, Great Bend, KS 67530

Company to plug at: Hour: 2:00 pm Day: 21 Month: June Year: 19 85

Plugging proposal received from LeRoy Borron

(company name) Blue Goose (phone) 316-792-5633

Elevation 2817

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 2162

1st plug at 2162' with 20 sx cement

2nd plug at 1355' with 80 sx cement

3rd plug at 446' with 40 sx cement
solid bridge

4th plug hulls - plug at 40' -- cement to surface with 10 sx cement

6th plug to circulate rat hole with 10 sx cement

Plugging Proposal Received by Richard W. Lacey

(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 4:30 pm Day: 21 Month: June Year: 19 85

ACTUAL PLUGGING REPORT 1st plug at 2162' with 20 sx cement, 2nd plug at 1355' with 80

sx cement, 3rd plug at 446' with 40 sx cement, 4th & 5th plugs - solid bridge - hulls -

plug at 40' -- cement to surface with 10 sx cement, 6th plug to circulate rat hole with

10 sx cement.

RECEIVED
STATE CORPORATION COMMISSION

7-1-85
JUL 01 1985

Remarks: Used 60/40 Pozmix 2% gel 3% cc by Allied.

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this form.)

INVOICED

(222/814 net) observe this plugging.

DATE 7-12-85

Signed Richard W. Lacey (TECHNICIAN)

INV. NO. 8917

6-21