

To: 1 051502  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
300 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

11-29  
API NUMBER 15-101-21,605-0000 159 R  
N/2 SE SW, SEC. 3, T 19 S, R 29 W/E

TECHNICIAN'S PLUGGING REPORT

Operator License # 6484

Operator: Anderson Energy, Inc.  
Name & Address 200 E. 1st St., Suite 414  
Wichita, KS 67202

990 feet from S section line  
1980 feet from E section line

Lease Name McWhirter Well # 1

County Lane 151.12

Well Total Depth 4650 feet

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 3 5/8 feet 335

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A X

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor White & Ellis Drilling, Inc. License Number 5420

Address P.O. Box 48848, Wichita, KS 67201-8848

Company to plug at: Hour: 4 a.m. Day: 29 Month: 11 Year: 19 91

Plugging proposal received from Judy

(company name) White & Ellis Drilling, Inc. (phone) 316-263-1102

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 2167-36'

1st plug at 2180' with 50 sx cement, 2nd plug at 1400' with 80 sx cement,

3rd plug at 700' with 40 sx cement, 4th plug at 360' with 50 sx cement,

5th plug at 40' with 10 sx cement,

6th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Richard Lacey  
(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None X

Operations Completed: Hour: 7:50 a.m. Day: 29 Month: 11 Year: 19 91

ACTUAL PLUGGING REPORT 1st plug at 2180' with 50 sx cement,

2nd plug at 1400' with 80 sx cement,

3rd plug at 700' with 40 sx cement,

4th plug at 360' with 50 sx cement,

5th plug at 40' with 10 sx cement,

6th plug to circulate rathole with 15 sx cement.

RECEIVED  
STATE CORPORATION COMMISSION  
DEC 03 1991  
12-3-91  
CONSERVATION DIVISION  
Wichita, Kansas

Remarks: Used 60/40 Pozmix 6% gel 1/2# floeal by Allied.

(If additional description is necessary, use BACK of this form.)

**INVOICED**  
I hereby certify to observe this plugging.

DATE 12-6-91

INV. NO. 34031

Signed Richard M. Lacey  
(TECHNICIAN)