

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
March 2009
Type or Print on this Form
Form must be Signed
All blanks must be Filled

OPERATOR: License #: 34202
Name: Kirkpatrick Oil Co., Inc.
Address 1: 1001 W. Wilshire Blvd, Suite 202
Address 2: _____
City: Oklahoma City State: OK Zip: 73116 + _____
Contact Person: Julie Lewis
Phone: (405) 767-3608 *KCC*
Type of Well: (Check one) Oil Well Gas Well OG D&A Cathodic
 Water Supply Well Other: dry hole SWD Permit #: _____
 ENHR Permit #: _____ Gas Storage Permit #: _____
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (if needed attach another sheet)
CIBP Depth to Top: 5160 Bottom: 5183 T.D. 5192
CIBP Depth to Top: 5205 Bottom: 5024 T.D. 5028
5214 Depth to Top: 5224 Bottom: 4964 T.D. 5024

API No. 15 - 077-21710-00-00
Spot Description: _____
C NW SW SE Sec. 2 Twp. 35 S. R. 5 East West
990 Feet from North / South Line of Section
2,310 Feet from East / West Line of Section
Footages Calculated from Nearest Outside Section Corner:
 NE NW SE SW
County: Harper
Lease Name: Turek Well #: 1-2
Date Well Completed: _____
The plugging proposal was approved on: _____ (Date)
by: _____ (KCC District Agent's Name)
Plugging Commenced: 1-18-2013
Plugging Completed: 1-22-2013

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
		SURF	8 5/8	325	-0-
		P C	5 1/2	5330	3928

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

MIRU. Pull tubing. Load hole. Set CIBP w/ 2 sk cmt 4900'. Pull slips and work pipe. Shot pipe at 4000'--couldn't pull. Shot pipe at 3928--lay down pipe. Run tubing to 1000'. Pump 35 sk cmt 1000 - 877. Pull to 695'. Pump 35 sk cmt 695 - 572. Pull to 375. Pump 120 sk 375 - 4. Cut off, cap & ID

Plugging Contractor License #: 34271 Name: Kivett Plugging & Pipe Pulling, Inc.
Address 1: P O Box 577 Address 2: 402 N. 13th St.
City: Blackwell State: OK Zip: 74631 + _____
Phone: (580) 763-7748
Name of Party Responsible for Plugging Fees: Kirkpatrick Oil Company, Inc.
State of Oklahoma County: Oklahoma ss. _____
Robert Cooksey Employee of Operator or Operator on above-described well,
(Print Name)

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: Robert Cooksey

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED
FEB 25 2013
KCC WICHITA