

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
130 S. Market, Room 2078  
Wichita, KS 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 5057-205540000

LEASE NAME McCaustland

WELL NUMBER 1-24

1320 Ft. from S Section Line

1520 Ft. from E Section Line

SEC. 24 TWP. 29S RGE. 22W (E) or (W)

COUNTY Ford

Date Well Completed \_\_\_\_\_

Plugging Commenced 10/24/99

Plugging Completed 10/24/99

RECEIVED  
STATE CORPORATION COMMISSION

NOV 10 1999  
11-10-99

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Conservation Division  
Coronado Petroleum Corporation

ADDRESS 105 N. Hudson, Suite 800

PHONE (405) 232-9700 OPERATORS LICENSE NO. 32521

Character of Well Dry

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 10/22/99 (date)

by Richard Lacey (KCC District Agent's Name).

Is ACO-1 filed? Yes if not, is well log attached? \_\_\_\_\_

Producing Formation NA Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ T.D. 5500

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
None				8 5/8"	676'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set. Mud weight in hole 9.0 PPG. 50 sks cmt. plug @ 1450', 50 sks cmt. plug @ 700', 10 sks cmt. plug @ 40', 10 sks cmt. in mouse hole, 15 sks cmt. in rat-hole, all cmt. 60/40 Pozmix w/6% gel, cut off surface casing 3' below ground level.

Name of Plugging Contractor Allen Drilling Company License No. 5418

Address P. O. Box 1389, Great Bend, Kansas 67530

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Coronado Petroleum Corporation

STATE OF Oklahoma COUNTY OF Oklahoma, ss.

(Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filled the the same are true and correct, so help me God.

DIANA L. THOMPSON  
CLEVELAND COUNTY  
Notary Public In And For  
The State Of Oklahoma  
SUBSCRIBED AND SWORN TO before me this 8th day of November, 1999

(Signature) Diana L. Thompson  
105 N. Hudson, Suite 800  
(Address) Oklahoma City, Okla. 73102

me this 8th day of November, 19 99  
Diana L. Thompson  
Notary Public

My Commission Expires: Nov. 18, 2000