



STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Sumner County, Sec. 5 Twp. 33S Rge. 4W (E) (W)

Location as "NE/CNWxSWx" or footage from lines C NE SW

Lease Owner Herndon Drilling Company

Lease Name Small Well No. 1

Office Address P. O. Box 489, Tulsa, Oklahoma

Character of Well (completed as Oil, Gas or Dry Hole) D & A

Date well completed 4/13/ 19 64

Application for plugging filed 4/13/ 19 64

Application for plugging approved 4/13/ 19 64

Plugging commenced 4/13/ 19 64

Plugging completed 4/13/ 19 64

Reason for abandonment of well or producing formation No commercial quantities of oil or gas encountered

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

NORTH

Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Howard Hess

Producing formation None Depth to top Bottom Total Depth of Well 4659 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS CASING RECORD

FORMATION	CONTENT	FROM	TD	SIZE	PUT IN	PULLED OUT
Surface		0	306	8-5/8"	306	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Heavy mud was put into the hole from a depth of 4659 to 300 feet where the bottom plug was set and cemented with 25 sacks cement. Mud was again put into the hole to a depth of 40 feet where the top plug was set and cemented with 15 sacks. Rat hole was plugged with 2 sacks cement. Surface pipe was cut off below ground level and the location abandoned.

RECEIVED
STATE CORPORATION COMMISSION

APR 20 1964

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Tomlinson-Kathol
Address 1125 Wichita Plaza, Wichita, Kansas

STATE OF Kansas COUNTY OF Sedgwick, ss.
Richard C. Davis (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature] 1125 Wichita Plaza, Wichita, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 16th day of April, 19 64

My commission expires Jan. 19, 1965 [Signature] Notary Public.



R

DRILLERS LOG
HERNDON DRILLING COMPANY
1 SMALL
C NE SW, SEC. 5-33S-4W
SUMNER COUNTY, KANSAS

Contractor - Tomlinson-Kathol, Inc.

Commenced: 3/30/64
Completed: 4/13/64
Elevation: 1269 KB

<u>From</u>	<u>To</u>	<u>Description</u>	<u>Remarks</u>
0	75	Shale	
75	306	Shale & Sand	
306	1130	Shale	308' 8-5/8" Surface Casing w/200 sacks cement
1130	2270	Lime and Shale	
2270	2500	Shale	
2500	2660	Shale & Lime	
2660	2777	Lime & Shale	
2777	2940	Shale & Lime	
2950	3100	Lime & Shale	
3100	3374	Shale & Lime	
3374	3490	Lime & Shale	
3490	3600	Shale & Lime	
3600	3816	Lime	
3916	4220	Lime & Shale	
4220	4260	Lime w/Shale	
4260	4648	Mississippian	
4649	4659	Simpson	
4659		Total Depth	

RECEIVED
STATE CORPORATION COMMISSION

APR 20 1964

CONSERVATION DIVISION
Wichita, Kansas

I certify to the best of my knowledge and belief, the above represents a true and accurate driller's log record of the captioned well.



Richard C. Davis

STATE OF KANSAS

SS

COUNTY OF SEDGWICK

Subscribed and sworn to before me this 16th day of April, 1964.



Esther Lamone, Notary Public

My Commission Expires: 1/19/65