

15-077-00280-0000


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

All Information Completely
Required Affidavit
Per Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

Harper County, Sec. 18 Twp. 32S Rge. 6W (E) (W)
Location as "NE/CNW/SW" or footage from lines SE SW
Lease Owner Texaco, Incorporated
Lease Name L. B. Hunter Well No. 1
Office Address 614 Bitting Building
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 11-16-63 19
Application for plugging filed 11-16-63 19
Application for plugging approved 11-16-63 19
Plugging commenced 11-16-63 19
Plugging completed 11-16-63 19
Reason for abandonment of well or producing formation Dry Hole



If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Archie Elving, Pratt, Kansas
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4911 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	355'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Mud to 300' Plug & 1/2 sack hulls & 25 sacks cement through drill pipe.
Mud to 40' & 1/2 sack hulls & 10 sacks cement. 5 sacks in Rathole.

RECEIVED
STATE CORPORATION COMMISSION

NOV 20 1963

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Leben Drilling, Inc.
Address P. O. Box 486, Great Bend, Kansas

STATE OF KANSAS, COUNTY OF BARTON, ss.
Leslie Kite (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Leslie Kite
P. O. Box 486, Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 18th day of November, 19 63

My commission expires April 1, 1967 Ulanda Nichols Notary Public.

DRILLER'S LOG

COMPANY: Texaco, Incorporated
 CONTRACTOR: LEBEN DRILLING, INC.
 FARM: L. B. HUNTER #1
 LOCATION: SE SW Sec. 18-32S-6W
 HARPER COUNTY, KANSAS
 COMMENCED: 10-31-63
 COMPLETED: 11-16-63

0	10	Red Shale
10	356	Redbed & Shale
356	500	Redbed
500	1160	Redbed & Shale
1160	1200	Anhydrite
1200	1210	Shale with Lime Streaks
1210	1465	Shale & Shells
1465	2050	Lime & Shale
2050	2305	Shale & Lime & Shells
2305	3375	Shale & Lime
3375	3710	Lime & Shale
3710	4436	Lime
4436	4446	Cherty Lime (Miss. Top @ 4437')
4446	4670	Lime
4670	4407	Lime & Chert
4407	4783	Lime
4783	4817	Shale & Lime
4817	4836	Lime & Shale
4836	4850	Shale & Sandy Lime
4850	4858	Sand
4858	4887	Simpson Sand
4887	4911	Sand
	<u>4911</u>	<u>Rotary Total Depth - D. & A.</u>

RECEIVED
 STATE CORPORATION COMMISSION
 NOV 20 1963
 CONSERVATION DIVISION
 Wichita, Kansas

Set 8 5/8" used 28# Surface Casing @ 355' with landing joint Cemented with 300 sacks Posmix with 2% c.c.

I, Leslie Kite, do hereby certify that the above and foregoing is a true and correct copy of the log of the L. B. Hunter #1 well, located in SE SW of Section 18, Township 32 South, Range 6 West, Harper County, Kansas, as reflected by the files of Leben Drilling, Inc.

Leslie Kite

Leslie Kite

STATE OF KANSAS)
 COUNTY OF BARTON) SS

Subscribed and sworn to before me, a Notary Public, in and for Barton County, Kansas, this 18th day of November, 1963.

Ulanda Nichols

Ulanda Nichols, Notary Public

My Commission Expires:
 April 1, 1967