

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, Kansas 67202

Well Plugging Record
K.A.R. -82-3-117

AND KCC

15-077-21308
15-007-21300000
Scoby
1

API NUMBER
LEASE NAME
WELL NUMBER

TYPE OR PRINT

NOTICE: Fill out completely and return
to Cons. Div. office within 30 days.

825 Ft. from S / N Line of Section (Circle one)
445 Ft. from E W Line of Section (Circle one)

LEASE OPERATOR Coral Coast Petroleum, L.C. SPOT LOCATION 825' FNL & 445' FEL from NE corner
ADDRESS 100 N. Main, Suite #505 Section 20 Township 32 Range 6w
CITY, STATE, ZIP Wichita Kansas 67202 County Harper
PHONE # (316) 269-1233 Date Well Completed July 11, 1996
Character of Well Dry and Abandoned Date Plugging Commenced July 11, 1996
(Oil, Gas, D&A, SWD, Input, Water Supply Well) Date Plugging Completed July 11, 1996

The plugging proposal was approved on July 8, 1996 at 2:30 pm (date)
by Gerold Clark (KCC District Agent's Name)

Is ACO-1 Filed? ? If not, is well log attached? Yes
Producing Formation(s) D&A Depth to Top Bottom T.D. 4900

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULL OUT
Top Soil and Redbed	No Sands	0	221	8-5/8"	204.23'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each set.

Heavy mud to 1175' then 35 sacks, heavy mud to 800' then 35 sacks, heavy mud to 270' then 35 sacks, heavy mud to 60' then 25 sacks. Using 60/40 Poz with 4% Gel. Plug rathole with 10 sacks.

(If additional description is necessary, use BACK of this form)

Name of Plugging Contractor Sterling Drilling Company
Licence No. 5142
Address P.O. Box 1006 City: Pratt State: Kansas Zip 67124

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Coral Coast Petroleum, L.C. (Operator)

STATE OF KANSAS COUNTY OF PRATT, ss.

Steve E. McClain, Agent (Employee of Operator or (Operator) of above described well, being first
duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of
the above described well as filed that the same are true and correct, so help me God.

(Signature) [Signature]
(Steve E. McClain, President of Sterling Drilling Company)

(Address) P.O. Box 1006 City: Pratt State: Kansas Zip 67124

SUBSCRIBED AND SWORN TO me this 27th day of August, 19 96



[Signature]
(Notary Public)

My Commission Expires: _____

RECEIVED
KANSAS CORP COM
1996 AUG 21 A 10:55

Sterling Drilling Company, Rig #4

Box 1006, Pratt, Kansas 67124-1006

Office Phone (316) 672-9508, Fax 672-9509

SAMPLE LOG

API# 15-077-21,3080000

#1 Scoby

LOCATION: 825' FNL & 445' FEL from NE S Section 20 T 32S R 6W
Harper County, Kansas

OWNER: Coral Coast Petroleum, L.C.

COMMENCED: 01-Jul-96

CONTRACTOR: Sterling Drilling Company, Rig #4

COMPLETED: 11-Jul-96

TOTAL DEPTH: DRILLER 4990 FEET

Elevation GL: 1430

LOGGER 4990 FEET

Elevation KB: 1439

LOG

0	-	221 FEET	Top Soil and Redbed (No water sands)
221	-	1585 FEET	Shale
1585	-	4850 FEET	Lime/Shale/Dolomite
4850	-	4990 FEET	Sandstone and Shales

CASING RECORDS

Spud @ 12:30 pm on 7-1-96. Drilled 12 1/4" hole to 221'. Ran 7 joints of Used 24# 8-5/8" surface casing 204.23' set at 216'KB. Cemented with 160 sacks 60/40 Poz, 2% Gel, 3% CC. Plug down at 6:15 pm on 7-1-96 by Allied. Good returns. Ticket # 4036.

Plugged well with 35 sacks at 1175', 35 sacks at 800', 35 sacks at 270', 25 sacks at 60' with 10 sacks in the rathole. Using 60/40 Poz with 4% Gel. Received plugging orders at 2:30pm on 7-8-96 from Gerold Clark - State Plugger. Started plugging well at 1:00 pm and completed plugging at 3:00pm on 7-11-96 by Allied Ticket # 3976.

RECEIVED
KANSAS CORP COM
1996 AUG 29 A 10:55

DEVIATION SURVEYS

1/2	Degrees	221 FEET
2-1/2	Degrees	3548 FEET
1	Degrees	3987 FEET
3/4	Degrees	4460 FEET

RECEIVED
KANSAS CORPORATION COMMISSION

AUG 15 1996

CONSERVATION DIVISION
WICHITA, KS