

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

WELL PLUGGING RECORD

Sumner County, Sec. 27 Twp. 31S Rge. (E) 1 (W)

Location as "NE/CNW*SW*" or footage from lines NE NE NE

Lease Owner Aladdin Petroleum Corporation

Lease Name Voils Well No. 1

Office Address 809 Petroleum Building, Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) oil

Date well completed April 14, 19 55

Application for plugging filed April 22, 19 66

Application for plugging approved April 25, 19 66

Plugging commenced May 3, 19 66

Plugging completed May 11, 19 66

Reason for abandonment of well or producing formation not profitable

If a producing well is abandoned, date of last production May 19 66

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Howard Hess

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3717 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	337	none
				5-1/2"	3716	2648'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Rock bridge 3118 to 3105'.
5 sacks cement 3105 to 3075'.
Pulled 2648' 5-1/2"
Mud 3075' to 250'.
Rock bridge 250 to 240'.
3-1/2 yards cement 240 to base of cellar.

RECEIVED
STATE CORPORATION COMMISSION
JUN 14 1966
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Glenn & Smith
Address Ellinwood, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
J. M. Johnson (employee of owner) or (owner's representative) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God!

(Signature) J. M. Johnson, Vice Pres.
809 Petroleum Building, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 13th day of June, 19 66.

Esther L. Marshall
Notary Public.

My commission expires Sept. 19, 1967.

27-31-1W

ROTARY DRILLING LOG

OPERATOR: Aladdin Petroleum Corporation
 Well #1
 NE NE NE Sec. 27-31-1W,
 Sumner County, Kansas

CONTRACTOR: Prime Drilling Company
 COMM: 4/3/55
 COMP: 4/14/55

<u>Formation</u>	
Shale & Sand	74
Shale & Shells	337
Lime & Sand	700
Lime & Shale	990
Lime	1264
Shale & Lime	1900
Lime	2055
Lime & Shale	2875
Shale & Lime Streaks	3050
Lime	3215
Lime & Shale	3320
Lime	3392
Lime & Shale	3670
Lime	3717
Rotary Total Depth	3717
Elev. 1268 GL	
1279 KB	
Top Mississippi Lime	3643
Perforated 3659-63 with 24 holes, squeezed	
150 sacks cement.	
Perforated 3649-64 with 67 holes.	
Acidized with 1000 gal.	
Potential 258 B/D May 18, 1955	

Remarks
 Set 8-5/8" surface casing at 337'
 with 325 sacks cement and 2% C.C.

Set 5-1/2" casing at 3716' with
 150 sacks pozmix.

We certify that the above log is
 true and correct to the best of our
 knowledge and belief.

PRIME DRILLING COMPANY

R.R. McNicol

R. R. McNicol

STATE RECEPTION COMMISSION
 JUN 14 1966
 CONSERVATION DIVISION
 Wichita, Kansas