

1 020143

5-3-88

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-175-21,027-0000

NE NE SW, SEC. 9, 'T 31 S, R 34 W/E
2310 feet from S section line
2970 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4549

Lease Name Behan Well # B-1

Operator: Anadarko Petroleum Corporation

County Seward 185.25

Name & Address P.O. Box 351

Well Total Depth 5700 feet

Liberal, KS 67901

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 1600

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Gabbert-Jones Inc. License Number 5842

Address English Key Bldg., Suite 215, Wichita, KS 67202

Company to plug at: Hour: 2:30 a.m. Day: 3 Month: 5 Year: 19 88

Plugging proposal received from Jim Barlow

(company name) Anadarko Petroleum Corporation (phone) 316-624-6253

work: to fill hole with heavy mud and spot cement through drill pipe Elevation 2820'

1st plug at 2760' with 100 sx cement, 2nd plug at 1569' with 50 sx cement,

3rd plug at 750' with 40 sx cement, 4th plug at 40-0' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement,

6th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Glenn Barlow
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 6:30 a.m. Day: 3 Month: 5 Year: 19 88

ACTUAL PLUGGING REPORT 1st plug at 2760' with 100 sx cement,

2nd plug at 1569' with 50 sx cement,

3rd plug at 750' with 40 sx cement,

4th plug at 40-0' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement,

6th plug to circulate mousehole with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Halliburton.
(if additional description is necessary, use BACK of this form.)

INVOICED
I (X) () () () observe this plugging.

Signed Glenn P Barlow
(TECHNICIAN)

RECEIVED
STATE CORPORATION COMMISSION
MAY 13 1988
5-13-88
CONSERVATION DIVISION
Wichita, Kansas

DATE 5-17-88

INV. NO. 20618

NOTICE OF INTENTION TO DRILL

(see rules on reverse side)

Expected Spud Date: 04/20/88
OPERATOR: License # 4549
Name: ANADARKO-PRODUCTION CO.
Address: P.O. BOX 351
City/State/Zip: IJERAI, 67901
Contact Person: J. R. JARSON
Phone: (713) 875-1101

API Number 15-175-21,027-0000
NE NE SW Sec 9 Twp 31 S. Rg 24 XX West
2310 Ft. from South Line of Section
2970 Ft. from East Line of Section

CONTRACTOR: License #
Name: Unknown
City/State:
Well Drilled For:
XX Oil Storage XX Infield XX Mud Rotary
Gas Inj Pool Ext Air Rotary
OWWO Expl Wildcat Cable

(Note: Locate well on Section Plat on reverse side)
Nearest lease or unit boundary line 2310 feet
County: SAKAON
Lease Name: BRADON Well # B-1
Ground surface elevation 7. est 2850 feet MSL
Domestic well within 330 feet: yes XX no
Municipal well within one mile: yes XX no
Depth to bottom of fresh water 400
Depth to bottom of usable water 550
Surface pipe by Alternate: 1 XX
Surface pipe planned to be set 1.640
Conductor pipe required
Projected Total Depth 5690 feet
Formation: St. Louis

If OWWO: old well info as follows:

Operator
Well Name
Comp Date Old Total Depth

I certify that well will comply with K.S.A. 55-101, et seq., plus eventually plugging hole to KCC specifications.

Date 4/15/88 Signature of Operator or Agent Title AGENT

For KCC Use:

Conductor Pipe Required feet; Minimum Surface Pipe Required 600 feet per Alt. 1 X

This Authorization Expires 10-26-88 Approved By 9-14-15-88

EFFECTIVE DATE: 4-20-88

Spud 4-20-88 Set PFP 1640 85%

Sec 9 Twp 31 S. Rg 24 XX West

PLUGGING PROPOSAL IF ABOVE IS D & A

This plugging proposal will be reviewed and approved or revised at the time the district office is called prior to setting surface casing (call 7 a.m. to 5 p.m. workdays).

Table with 4 columns: Plug depth, Formation, Circulation, and Plug type. Includes entries for 1st through 5th plugs and Rathole/Mousehole to surface minus 5 feet.

PUSHER Jim Barlow
TD 5700 FORMATION St Lewis
SURFACE PIPE 8 3/8 @ 15 1600
ANEHYDRITE ELEVATION 2820
STARTING TIME & DATE 5-3-88 2:30 PM
COMPLETION TIME & DATE 5-3-88 6:30 AM
1st PLUG @ 2760 FT. W/ 100 SX
2nd PLUG @ 1569 FT. W/ 50 SX
3rd PLUG @ 750 FT. W/ 40 SX
4th PLUG @ 40-0 FT. W/ 10 SX
RAT HOLE CIRCULATED W/ 15 SX
MOUSE HOLE CIRCULATED W/ 10 SX
WATER WELL PLUGGED W/ 20 SX
CEMENT COMPANY Hall
TECHNICIAN 60/40 w/ 6 3/4 gell

RECEIVED
STATE CORPORATION COMMISSION
MAY 13 1988
CONSERVATION DIVISION
Wichita, Kansas