

15-155-00305-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Biting Building
Wichita, Kansas

Reno County, Sec. 14 Twp. 22 Rge. 8 (E) W (W)

Location as "NE/CNW/SWK" or footage from lines NE/4 NW/4 NE/4

Lease Owner Transit Corporation & Davis Bros.

Lease Name Welker Well No. 1

Office Address 1516 Liberty Bank Bldg., Okla. City, Okla.

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 8-9 19 52

Application for plugging filed 8-9 19 52

Application for plugging approved 8-9 19 52

Plugging commenced 8-9 19 52

Plugging completed 8-9 19 52

Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Ruel Durkee, Box 597, McPherson, Kansas

Producing formation Depth to top Bottom Total Depth of Well 3640 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8	288'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled Hole with heavy drilling mud to 240' set plug and cemented with 15 sacks cement. Filled hole with heavy drilling mud to 12' from bottom of cellar, set plug and cemented with 5 sacks cement to bottom of cellar.

RECEIVED
STATE CORPORATION COMMISSION
WICHITA, KANSAS
8-12-52

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Transit Corporation
Address 1516 Liberty Bank Bldg., Okla. City, Okla.

STATE OF Oklahoma COUNTY OF Oklahoma ss.
L. J. Kruse (employee of owner) or (owner/conservator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]
Oklahoma City, Okla.
(Address)

SUBSCRIBED AND SWORN TO before me this 11th day of August, 19 52

My commission expires October 24, 1955 [Signature] Notary Public.

PLUGGING
FILE SEC 14 T 22 R 8
BOOK PAGE 57 LINE 16

TRANSIT CORPORATION & DAVIS BROTHERS

NE/4 NW/4 NE/4 Sec. 14-22S-8W
Reno County, Kansas

WELKER NO. 1

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Surface Clay & Sand	0	40	8-5/8" C.S.A. @ 288'. Cemented with 175 Sacks Cement.
Shale Shells & Sand	40	254	
Shale Sand Shells	254	650	
Shale & Shells	650	815	
Salt & Shale	815	995	
Shale & Lime	995	1260	
Lime	1260	1510	
Lime & Shale	1510	1560	
Lime	1560	1635	
Shale & Lime	1635	1735	
Shale & Shells	1735	2155	
Shale & Lime	2155	2580	
Lime & Shale	2580	2715	
Lime	2715	2785	
Shale & Lime	2785	2880	
Lime & Shale	2880	2911	
Sandy Shale	2911	2971	
Lime & Shale	2971	3035	
Shale & Lime	3035	3058	
Lime & Shale	3058	3105	
Lime	3105	3475	
Lime & Shale	3475	3550	
Conglomerate	3550	3565	
Lime & Chert	3565	3585	
Conglomerate	3585	3600	
Lime & Chat	3600	3620	
Shale & Lime	3620	3640	
Total Depth		3640'	

I hereby certify the foregoing to be a true and accurate Driller's Log of the formations encountered in the above well.

TRANSIT CORPORATION

By: L. J. Kruse
L. J. Kruse
Ass't Secretary

RECEIVED
STATE CORPORATION COMMISSION
AUG 12 1952
CONSERVATION DIVISION
Wichita, Kansas

PLUGGING
FILE SEC 14-22-8W
BOOK PAGE 37 LINE 16

Subscribed and sworn to before me this 11th day of August, 1952

William Wright
Notary Public

My Commission Expires: October 24, 1955