

STATE OF KANSAS
STATE CORPORATION COMMISSION


Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
P. O. Box 17027
Wichita, Kansas 67217
NORTH

WELL PLUGGING RECORD

Summer County, Sec. 25 Twp. 33 Rge. 4 (E) (W)
SE SE NE

Location as "NE/CNW/SW" or footage from lines
Lease Owner Dorset Company
Lease Name Walta #1 Well No.
Office Address Tulsa, Oklahoma 74103
Character of Well (completed as Oil, Gas or Dry Hole)
Date well completed 19
Application for plugging filed 19
Application for plugging approved 19
Plugging commenced ~~7/22~~ 7/20/73 19
Plugging completed 7/26/73 19
Reason for abandonment of well or producing formation depleted.



Locate well correctly on above Section Plot

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Graham
Producing formation Depth to top Bottom Total Depth of Well 4512 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8	202	none
				5 1/8	4505	3882

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Checked hole, sanded to 4000' and set 5 sacks cement.
Shot pipe at 3935', 3870', pulled 120 joints. Set rock bridge 220 to 210' and ran 25 sacks cement. Mud to 40', rock bridge and ran 10 sacks cement.

PLUGGING COMPLETE.

RECEIVED
STATE CORPORATION COMMISSION
AUG 8 1973
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor VOTH CASING PULLING
Address CHASE, KANSAS

STATE OF KANSAS COUNTY OF RICE ss.
WALTER VOTH (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Walter Voth
CHASE, KANSAS
(Address)

SUBSCRIBED AND SWORN to before me this 31st day of July, 1973

My commission expires
MARGARET MELCHER
NOTARY PUBLIC
Rice County, Kansas
My Commission Expires
Feb. 15, 1975

Margaret Melcher
Notary Public.

WALTA #1
SE SE NE Sec. 25-339-4W
Sumner County, Kansas

Operator: Dorset Company
Contractors: McKnab - Lindsay

Date Comm: 7-21-59
Date Under Surf: 7-22-59
Date Comp: 8-10-59

DRILLER'S LOG:

0 - 210	Surface Hole
210 - 725	Shale & Shells
725 - 1800	Shale & Lime
1800 - 2035	Shale & Sand
2035 - 2220	Shale & Lime
2220 - 2370	Shale & Shells
2370 - 2754	Shale & Lime
2754 - 2763	Shale
2763 - 2820	Shale & Lime
2820 - 2870	Chalky Lime
2870 - 3185	Shale & Lime
3185 - 3214	Sand & Shale
3214 - 3272	Shale & Lime
3272 - 3325	Shale & Sand
3325 - 3438	Shale & Lime
3438 - 3525	K. C. Lime
3525 - 3552	Chalky Lime
3552 - 3572	Brown Lime
3572 - 3698	K.C. Lime
3698 - 4105	Shale & Lime
4105 - 4388	Miss. Lime
4388 - 4477	Lime
4477 - 4504	Shale & Lime
4504 - 4505	Lime
4505 - 4512	Simpson Sand
4512	T.D.

Casing & Cement Record

10 jts. 8 5/8" casing 202' set at 210' cemented with 160 sks. HA 500

141 jts. 8 rd thd. 1 1/2" 5 1/2" casing set at 4505.5' with 180 sks. pozmix cement.

RECEIVED
CORPORATION COMMISSION
JUL 9 1973
CONSERVATION DIVISION
Wichita, Kansas

Acknowledged:
McKnab & Lindsay

By E. J. Lindsay

Date: August 12, 1959

Subscribed and Sworn to before me this 12th day of August, 1959.

M. J. Liban
Notary Public

My Commission Expires Aug. 21, 1961.

4/22/68 P.B. to test Miss. Set Baker plug @ 4280'
Perf. 4168-78 4 shot/ft. - Treated w/ 250 gal mud acid - broke @ 2000' + finished @ 500' - No show
T.A.