

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-101-21,548 0000

LEASE NAME DIMMICK "D"

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER #1

650' Ft. from S Section Line

660' Ft. from E Section Line

LEASE OPERATOR SLAWSON EXPLORATION COMPANY, INC.

SEC. 10 TWP. 19 SRGE. 29 (X) or (W)

ADDRESS 104 S. BROADWAY, SUITE 200

COUNTY LANE

PHONE#(316) 263-3201 OPERATORS LICENSE NO. 3988

Date Well Completed 6-14-90

Character of Well D&A

Plugging Commenced 6-14-90

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 6-14-90

The plugging proposal was approved on June 13, 1990 (date)

by Richard Lacey (KCC District Agent's Name).

Is ACO-1 filed? by operator If not, is well log attached? _____

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 4650'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
Surface		0	302'	8 5/8"	302'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

50 sx. @ 2180', 80 sx. @ 1260', 40 sx. @ 660', 50 sx. @ 330', 10 sx. @ 40', 15 sx. in rat-hole
Total 245 sx. 60/40 Pozmix, 6% Gel, 1/4# celloflake per sx.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Allied Cementing License No. 6-26-90

Address Russell, Kansas 67665


NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Slawson Exploration Company, Inc.

STATE OF KANSAS COUNTY OF BARTON, ss.

Greg Davidson (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Greg Davidson

(Address) Great Bend, Kansas 67530



SUBSCRIBED AND SWORN TO before me this 18th day of June, 1990

Bessie M. DeWerff
Notary Public
Bessie M. DeWerff

My Commission Expires: 5-20-93

15-101-21548-0000

DRILLER'S WELL LOG

0 - 302 Surface
302 - 985 Shale
985 - 1965 Shale W/Lime Streaks
1965 - 2158 Shale
2158 - 2183 Anhy.
2183 - 4650 Lime & shale
4650 R.T.D.

SLAWSON EXPLORATION COMPANY, INC.
Dimmick "D" #1
C SE SE Sec. 10-19S-29W
Lane County, Ks.

Elevation: 2815' GR 2820' KB

FORMATION DATA: (sample)

Anhy	2157	(+663)
Base Anhy	2183	(+637)
Topeka	3708	(-888)
Heebner	3954	(-1134)
Toronto	3966	(-1146)
Lansing	3996	(-1176)
Muncie Ck	4175	(-1355)
Stark	4275	(-1455)
Hushpuckney	4313	(-1493)
BKC	4358	(-1538)
Marmaton	4382	(-1562)
Altamont	4429	(-1609)
Pawnee	4473	(-1653)
Cherokee	4543	(-1723)
Johnson	4581	(-1761)
Miss. (antic)	4610	(-1790)

SURFACE CASING:

8 5/8" Set # 302' W/175 sx. 60/40
Pozmix, 2% Gel, 3% CC

RECEIVED
STATE COMMISSIONER OF GEOLOGY
JUN 26 1990
GEOLOGICAL SURVEY
TOPEKA, KANSAS

A F F I D A V I T

STATE OF KANSAS)
COUNTY OF BARTON) ss

GREG DAVIDSON of lawful age, does swear and state that the facts and statements herein are true and correct to the best of his knowledge.

Greg Davidson
Greg Davidson

Subscribed and sworn to before me this 18th day of June, 1990.



My Commission expires: 5-20-93

Bessie M. DeWerff
Notary Public: Bessie M. DeWerff

EFFECTIVE DATE: 5-22-90

FORM MUST BE TYPED
FORM C-1 12/88

State of Kansas 101-21,548-0002

FORM MUST BE SIGNED
ALL BLANKS MUST BE FILLED

NOTICE OF INTENTION TO DRILL

Must be approved by the K.C.C. five (5) days prior to commencing well

Expected Spud Date May 21 1990
month day year

C SE SE Sec 10 Twp 19 S, Rg 29 East West

OPERATOR: License # 3988
Name: SLAWSON EXPLORATION COMPANY, INC.
Address: 104 S. Broadway, Suite 200
City/State/Zip: Wichita, Kansas 67202-4165
Contact Person: Bob Jenkins
Phone: (316) 263-3201

650' feet from South line of Section
660' feet from East line of Section
(Note: Locate well on Section Plat Below)

CONTRACTOR: License #: 6039
Name: L.D. DRILLING, INC.

County: Lane
Lease Name: DIMMICK "D" Well #: 1
Field Name: Wildcat

Is this a Prorated Field? yes X no
Target Formation(s): MISSISSIPPIAN

Well Drilled For: Well Class: Type Equipment:
X Oil ... Inj ... Infield X Mud Rotary
... Gas ... Storage ... Pool Ext. ... Air Rotary
... OAWO ... Disposal X Wildcat ... Cable
... Seismic; ... # of Holes

Nearest lease or unit boundary: 660'
Ground Surface Elevation: 2812' GR (Seis) det MSL
Domestic well within 330 feet: yes X no
Municipal well within one mile: yes X no

Depth to bottom of fresh water: 180'
Depth to bottom of usable water: 1150'

Surface Pipe by Alternate: 1 X 2
Length of Surface Pipe Planned to be set: 300'

Length of Conductor pipe required: None
Projected Total Depth: 4650'

If OAWO: old well information as follows:
Operator:
Well Name:
Comp. Date: Old Total Depth

Formation at Total Depth: Mississippian

Water Source for Drilling Operations:
Irrigation X well ... farm pond ... other

DWR Permit #: 32-189

Directional, Deviated or Horizontal wellbore? yes X no
If yes, total depth location:

Will Cores Be Taken?: yes X no
If yes, proposed zone:

Exp: 11/17/90

AFFIDAVIT

200' Alt. II Req.

The undersigned hereby affirms that the drilling, completion and eventual plugging of this well will comply with K.S.A. 55-101, et. seq.

Pusher J. Dawson

SPUD DATE 6-4-90 INIT. JD

LENGTH SURFACE PLANNED 300 F

RESERVE PIT STATUS- REMOVE FLUID LINED
after salt sect. bbls. when done bbls.

RATHOLED AHEAD? Y N SIZE HOLE
SURFACE PIPE 8 1/2 @ 302 CONDUCTOR
ANHYDRITE T- 2158 B- 2183 ELEVATION

TD 4650 FORMATION

RAPE	@	DV TOOL	ALT II DONE
			SX Y N
Arbuckle Plug @			Ft. W/ SX
Hug./Council @			Ft. W/ SX
Anhydrite Base @	<u>2180</u>		Ft. W/ <u>50</u> SX
1/2 Base Anyh. @	<u>1260</u>		Ft. W/ <u>80</u> SX
1/2, 1/2 Plug @	<u>660</u>		Ft. W/ <u>40</u> SX
Bottom Surface @	<u>330</u>		Ft. W/ <u>50</u> SX
40' Plug @	<u>40</u>		Ft. W/ <u>10</u> SX

RAT HOLE CIRC/W 15 SX MOUSE HOLE W/ SX

WATER WELL SX (Irr. Well Pond Hauling)

TECHNICIAN R.L. DATE 6-13-90

TYPE OF CEMENT 60/40 6% 1/4 Flowseal

STARTING TIME 12:00 (AM/PM) DATE 6-14-90

COMPLETION TIME 2:00 (AM/PM) DATE 6-14-90

CEMENT COMPANY Alfred