

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-191-21052 ²¹⁵⁰²⁰⁰⁰¹

LEASE NAME Kolarik

WELL NUMBER 1

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

1980 Ft. from S Section Line

1426 Ft. from E Section Line

LEASE OPERATOR Robert Schulgin

SEC. 16 TWP. 34 RGE. 4 (E) or (W)

ADDRESS 1776 Lincoln St #811 Denver, CO 80203

COUNTY Sumner

PHONE# (303) 839-5495 OPERATORS LICENSE NO. 6785

Date Well Completed _____

Character of Well oil

Plugging Commenced 3-8-94

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 3-9-94

The plugging proposal was approved on 3-8-94 (date)

by Steve Van Gieson (KCC District Agent's Name).

Is ACO-1 filed? yes If not, is well log attached? _____

Producing Formation Mississippi Depth to Top 4456' Bottom 4540' T.D. 4876'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
<u>Miss 4456'-4540'</u>	<u>oil-water-gas</u>	<u>Surface</u>	<u>298'</u>	<u>8 5/8"</u>	<u>298'</u>	<u>-0-</u>
		<u>Surface</u>	<u>4842'</u>	<u>4 1/2"</u>	<u>4842'</u>	<u>3370'</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each set.

Set CIBP @ 4400' + 2 sack Cement. Fresh water to 871' - 35 sack to 741'
Fresh water to 584' - 35 sack Cement to 454'. Fresh water to 378' - 115 sack
Cement to surface.
Note: CIBP @ 4610.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Shawnee Well Service License No. 30346

Address Attica, KS 67009

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Robert Schulgin

STATE OF _____ COUNTY OF _____, ss.

Carl W. Durr


(Employee of Operator) or _____

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as _____ that the same are true and correct, so help me God.

(Signature) Carl W. Durr

(Address) Milton, KS 67106

SUBSCRIBED AND SWORN TO before me this 18th day of March, 19 94



Sumner KS

Maurice Coulter
Notary Public

My Commission Expires: April 13th 1996

RECEIVED
STATE CORPORATION COM
MAR 21 1994
CONSERVATION DIVISION
Wichita, Kansas