

API NUMBER 15-101-21,650 - 0000

LEASE NAME PARIS

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

WELL NUMBER 1

1650 Ft. from (S) Section Line

330 Ft. from (E) Section Line

SEC. 11 TWP. 19S RCE. 29 XX or (W)

COUNTY LANE

LEASE OPERATOR Argent Exploration, Inc.

ADDRESS 110 South Main, Suite 810 Wichita, KS. 67202

PHONE (316) 262-5111 OPERATORS LICENSE NO. 30269

Character of Well D&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Date Well Completed 6-02-93

Plugging Commenced 6-02-93

Plugging Completed 6-02-93

The plugging proposal was approved on 6-01-93 (date)

by Steve Middleton (KCC District Agent's Name)

Is ACO-1 filed? by operator If not, is well log attached? yes

Producing Formation _____ Depth to Top _____ Bottom T.D. 4648'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| Formation | Content | From | To | Size | Put In | Pulled out |
|-----------|---------|------|-----|--------|--------|------------|
| surface | | 0 | 217 | 8 5/8" | 217' | none |
| | | | | | | |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from ___ feet to ___ feet each set.

50 sx. @ 2170', 80 sx. @ 1350', 40 sx. @ 670', 50 sx. @ 240', 10 sx. @ 40', 15 sx. in rat hole
Total: 245 sx. 60/40 Pozmix, 6% Gel, 1/4# floseal per sack Allied Cementing Co

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor L. D. Drilling, Inc. License No. 6039

Address R. R. 1 Box 183 B Great Bend, KS. 67530


NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Argent Exploration, Inc.

STATE OF Kansas COUNTY OF Barton, ss.

L. D. Davis (Employee of Operator) or (~~Operator~~) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) L. D. Davis

(Address) R.R. 1 Box 183 B **RECEIVED** KS 67530



SUBSCRIBED AND SWORN TO before me this 7th day of June 6-9-93, 1993

Bessie M. Dowerff
 Notary Public

My Commission Expires: 5-20-97

STATE CORPORATION COMMISSION
WICHITA DIVISION
 Wichita, Kansas

EFFECTIVE DATE: 5-25-93
DISTRICT # 3647 Yes No

State of Kansas
NOTICE OF INTENTION TO DRILL 101-21,650-0000 ALL BLANKS MUST BE FILLED

Must be approved by the X.C.C. five (5) days prior to commencing well

Expected Spud Date May 26 1993
month day year

SE NE SE Sec 11 Twp 19 S. Rq 29 East X West

OPERATOR: License # 30269
Name: Argent Energy, Inc.
Address: 110 South Main, Suite 810
City/State/Zip: Wichita, Kansas 67202
Contact Person: James C. Remsberg
Phone: (316) 262-3111

1650 feet from South North line of Section
330 feet from East West line of Section
IS SECTION X REGULAR IRREGULAR?

CONTRACTOR: License #: 6039
Name: L. D. Drilling, Inc.

(NOTE: Locate well on the Section Plat on Reverse Side)
County: Lane
Lease Name: Paris Well #: 1
Field Name: unnamed

Well Drilled For: Well Class: Type Equipment:
X Oil ... Enh Rec ... Infield X Mud Rotary
... Gas ... Storage ... Pool Ext. ... Air Rotary
... OWWO ... Disposal X Wildcat ... Cable
... Seismic; ... # of Holes ... Other
... Other

Is this a Prorated/Spaced Field? ... yes X no
Target Formation(s): Mississippian
Nearest lease or unit boundary: 330
Ground Surface Elevation: 2798 feet MSL

If OWWO: old well information as follows:
Operator: _____
Well Name: _____
Comp. Date: _____ Old Total Depth _____

Water well within one-quarter mile: ... yes X no
Public water supply well within one mile: ... yes X no
Depth to bottom of fresh water: 70
Depth to bottom of usable water: 1300

Directional, Deviated or Horizontal wellbore? ... yes X no
If yes, true vertical depth: _____
Bottom Hole Location: _____

Surface Pipe by Alternate: ... 1 X 2
Length of Surface Pipe Planned to be set: (.220) 200'
Length of Conductor pipe required: None
Projected Total Depth: 4600

Formation at Total Depth: Mississippian
Water Source for Drilling Operations:
... well ... farm pond X other

DWR Permit #: _____
Will Cores Be Taken? ... yes X no
If yes, proposed zone: _____

200' Alt. II Req.

AFFIDAVIT

Exp. 11/20/93

The undersigned hereby affirms that the drilling, completion and eventual plugging of this well will comply with K.S.A. 55-101, et. seq.

Pusher Bessie 650

SPUD DATE 5-26-93 INIT. Sm

LENGTH SURFACE PLANNED 200'

RESERVE PIT STATUS- REMOVE FLUID LINED
after salt sect. bbbls. when done bbbls.

RATHOLED AHEAD? Y N SIZE HOLE
SURFACE PIPE 8 1/2" 217 CONDUCTOR
ANHYDRITE T- B-2183 ELEVATION

TD 4648 FORMATION MISS

RAN PIPE @ SX DV TOOL SX ALT II DONE Y N

Arbuckle Plug @ _____ Ft. W/ SX

Hug./Council @ _____ Ft. W/ SX

Anhydrite Base @ 2170 Ft. W/ 50 SX

1/2 Base Anyh. @ 1350 Ft. W/ 80 SX

1/2, 1/2 Plug @ 670 Ft. W/ 40 SX

Bottom Surface @ 240 Ft. W/ 50 SX

40' Plug @ 40 Ft. W/ 10 SX

RAT HOLE CIRC/W 5 SX MOUSE HOLE W/ 10 SX

WATER WELL _____ SX (Irr. Well _____ Pond _____)
Hauling _____

TECHNICIAN Sm DATE 6-1-93

TYPE OF CEMENT 6940 67 1/2 16 Flossid

STARTING TIME 1:00 (AM/PM) DATE 6-2-93

COMPLETION TIME 3:30 (AM/PM) DATE 6-2-93

CEMENT COMPANY Allied

RECEIVED
JUN 4 1993
WICHITA, KANSAS
REGISTRATION DIVISION
COMMISSION

DRILLER'S WELL LOG

15-101-21650-0000

COMMENCED: 5-26-93
COMPLETED: 6-02-93

ARGENT EXPLORATION, INC.
PARIS #1
SE NE SE
SEC. 11-T19S-R29W
LANE COUNTY, KS.

- 0 - 217 Surface Shales
- 217 - 431 Sand & Shales
- 431 - 1170 Shale
- 1170 - 1890 Shale & sand
- 1890 - 2136 Shales
- 2136 - 2163 Anhy
- 2163 - 2675 Lime & Shale
- 2675 - 3870 Lime & Shale
- 3870 - 4015 Lime W/shale
- 4015 - 4648 Lime
- 4648 RTD

ELEVATION: 2794 GL 2799 KB

CASING:

8 5/8" set @ 217' W/145 sx. 60/40
Pozmix, 2% gel, 3% cc

AFFIDAVIT

STATE OF KANSAS)
COUNTY OF BARTON)SS


L. D. DAVIS of lawful age, does swear and state that the facts and statements herein are true and correct to the best of his knowledge.

L. D. Davis
L. D. Davis

Subscribed and sworn to before me this 7th day of June, 1993.

My Commission expires: 5-20-97

Bessie M. DeWerff
Notary Public: Bessie M. DeWerff



RECEIVED
STATE CORPORATE COMMISSION
JUN 9 1993
CONSERVATION DIVISION
Wichita, Kansas