

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

Summer County. Sec. 2 Twp. 31S Rge. (E) 2 (W)

Location as "NE/CNW&SW" or footage from lines. NW SW NE

Lease Owner Richard King, Inc.

Lease Name Myers Well No. 2

Office Address Box 2008, McAllen, Texas

Character of Well (completed as Oil, Gas or Dry Hole) Dry hole

Date well completed 12-1-58 19

Application for plugging filed 12-1-58 19

Application for plugging approved 12-1-58 19

Plugging commenced 12-1-58 19

Plugging completed 12-1-58 19

Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Fred Hampel, Pretty Prairie, Kansas

Producing formation Depth to top Bottom Total Depth of Well Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Mud	4211' - 240'
Cement	240 - 195
Mud	195 - 40
Cement	40 - 0

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor McKnab & Lindsay - Rotary Plugged

Address Box 808, Winfield, Kansas

STATE OF Kansas, COUNTY OF Cowley, ss.

V. W. McKnab (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) E. T. Lindsay

Box 808, Winfield, Kansas

SUBSCRIBED AND SWORN TO before me this 2nd day of December 1958

My commission expires Aug. 21, 1961

RECEIVED  
STATE CORPORATION COMMISSION  
DEC 5 1958  
CONSERVATION DIVISION  
Wichita, Kansas  
Notary Public.

PLUGGING  
FILE SEC 2 T 31 R 2W  
BOOK PAGE 1 LINE 31

WELL RECORD  
 MYERS #2  
 NW SW NE  
 2-318-2W  
 Sumner County, Kansas

Operator: Richard King, Inc.  
 Contractor: McKnab & Lindsay

Date Comm: 11-14-58  
 Date Under Surf: 11-16-58  
 Date Completed: 12-2-58

DRILLER'S LOG:

0 - 1333	Shale & Lime
1333 - 1843	Shale, sand & Lime
1843 - 2055	Shale & Lime
2055 - 2250	Shale, sand & Lime
2250 - 2681	Shale & Lime
2681 - 2950	Shale, sand & Lime
2950 - 3087	Shale
3087 - 3358	K. G. Lime
3358 - 3749	Lime & Shale
3749 - 3783	Core #1
3783 - 3826	Lime & Sahel
3826 - 4118	Mississippi Lime
4118 - 4198	Lime & Sahel
4198 - 4209	Core #2
4209 - 4211	Core #3
4211	T.D.

Casing Records:

20 Jts. used 10 3/4 10 THD & 8 THD  
 set @ 449' cemented with 325 sks  
 HA 5 - pumped plug to 400' split  
 landing joint - let cement equalize  
 Welox perforated pipe and Halliburton  
 recemented with 250 sks HA 500.

Plugging Records:

Mud	4211 - 240
Cement	240 - 195
Mud	195 - 40
Cement	40 - 0

ACKNOWLEDGED:

McKnab & Lindsay

By E. J. Lindsay

Date: December 3, 1958

Subscribed and sworn to before me this 3rd day of December, 1958.

Walter L. Libau  
 Notary Public

My Commission expires Aug. 21, 1961.

PLUGGING			
FILE	SEC	2 T 31	R 2W
BOOK	PAGE	1	LINE 31

RECEIVED  
 STATE CORPORATION COMMISSION  
 DEC 5 - 1958  
 CONSERVATION DIVISION  
 Wichita, Kansas