


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above Section Plat

Location as "NE/CNW/SW" or footage from lines Summer County. Sec 2 Twp. 31 Rge. 2 (E)W (W)
Lease Owner Falcon Seaboard Drilling Company
Lease Name Myers Well No. 2
Office Address P. O. Box 3348 Houston, Texas 77001
Character of Well (completed as Oil, Gas or Dry Hole) Oil
Date well completed May 22 19 58
Application for plugging filed July 30 19 68
Application for plugging approved August 5 19 68
Plugging commenced August 21 19 68
Plugging completed August 23 19 68
Reason for abandonment of well or producing formation No longer a Producer

If a producing well is abandoned, date of last production July 15 19 68
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Howard Hess
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3225' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				10 3/4	560'	None
				7	3225'	2116'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plugged back with sand from 3225' to 3200'. Mixed and dumped 5 sx. of cement from 3200' to 3170'. Pulled casing. Mudded hole to 260'. Set 10' rock bridge from 260' to 250'. Mixed and dumped 25 sx. of cement from 250' to 200'. Mudded hole from 200' to 30'. Set 10' rock bridge from 30' to 20'. Mixed and dumped 8 sx. of cement from 20' to base of the cellar.

RECEIVED
STATE CORPORATION COMMISSION
SEP 23 1968
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Russ Casing Pulling, Inc.
Address Box 1082 Great Bend, Kansas

STATE OF TEXAS, COUNTY OF HARRIS, ss.
J. A. Couvillon, Division Engineer (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) J. A. Couvillon
Box 3348 Houston, Texas 77001
(Address)

SUBSCRIBED AND SWORN TO before me this 20 day of September, 1968

My commission expires June 1969

Imogene Philip
Notary Public.

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

15-191-01200-0000


COPY

Company- FALCON SEABOARD DRILLING CO.
Farm- Myers No. 2

SEC. 2 T. 31 R. 2W
SW SE NE

Total Depth. 3224'
Comm. 5-13-50 Comp. 5-27-50
Shot or Treated.
Contractor. Falcon Seaboard Drig. Co.
Issued. 5-30-59

County Sumner KANSAS



CASING:

10 3/4" @ 582'
7" @ 3216'

Elevation. 1321' DE

Production. 60 BOPD

Figures Indicate Bottom of Formations.

surface soil & red bed	45
red bed, shale & shells	505
shale & shells	1039
shale	1210
shale & shells	1301
shale	1622
shale & lime	1928
sand, shale & lime	2056
shale & lime	2630
shale	2745
shale	3165
lime	3187
lime & shale	3217
lime	3220
lime	3224
Total Depth	

TOPS: SCOUT
Kansas City 3215

RECEIVED
STATE CORPORATION COMMISSION
AUG 12 1968
CONSERVATION DIVISION
Wichita, Kansas