

STATE OF KANSAS
STATE CORPORATION COMMISSION
206 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

7 API NUMBER 15-191,22,177-

LEASE NAME Wilkerson

WELL NUMBER 2

330 Ft. from S Section Line

330 Ft. from E Section Line

SEC. 13 TWP. 31S RGE. 2 ~~XXXX~~ (W)

COUNTY Sumner

Date Well Completed 11-2-90

Plugging Commenced 11-2-90

Plugging Completed 11-2-90

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Zenith Drilling Corporation

ADDRESS 100 N. Broadway - Suite 505, Wichita, KS

PHONE#(316) 265-6697 OPERATORS LICENSE NO. 5141

Character of Well D & A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on November 2, 1990 (date)

by Mr. Worley (KCC District Agent's Name).

Is ACO-1 filed? No If not, is well log attached? No

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 3789'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8"	416'	None

RECEIVED

STATE CORPORATION COMMISSION

NOV 9 1990 11-09-90

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from ___ feet to ___ feet each set.
Spotted 45 sx. cement @ 500' thru drill pipe.
Spotted 25 sx. cement @ 60' thru drill pipe.
Spotted 10 sx. cement in rathole

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor White & Ellis Drilling, Inc. License No. 5420

Address 401 E. Douglas - Suite 500, Wichita, KS 67202

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Zenith Drilling Corporation

STATE OF Kansas COUNTY OF Sedgwick, ss.

Michael L. Considine (Employee of Operator) ~~XXXXXXXXXX~~ of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.


(Signature) Michael L. Considine


(Address) 401 E. Douglas - Suite 500
Wichita, KS 67202

SUBSCRIBED AND SWORN TO before me this 6th day of November, 19 90

Carolyn J. Tjaden
Notary Public

My Commission Expires:





WHITE

ANDELLIS DRILLING, Inc.

DRILLERS LOG

OPERATOR: Zenith Drilling Corp., 100 N. Broadway - #505, Wichita, KS
 CONTRACTOR: White & Ellis Drilling, Inc. 401 E. Douglas - Suite 500
 Wichita, Kansas 67202

Lease Name Wilkerson Well No. 2
 Sec. 13 T. 31S R. 2W Spot SE SE SE
 County Sumner State Kansas Elev. _____

Casing Record:

Surface: 8 5/8" @ 416' with 300 sx.
 Production: _____ @ _____ with _____ sx.

Type Well: D & A Total Depth 3789'
 Drilling Commenced 10-24-90 Drilling Completed 11-2-90

Formation	From	To	Tops
Cellar	0	5	Stalnaker 2810
Shale	5	604	Kansas City 3102
Shale & Lime Streaks	604	1475	Marmaton 3425
Shale & Lime	1475	2220	Mississippi 3773
Lime & Shale	2220	2615	
Shale & Lime	2615	2810	
Sand	2810	2890	
Shale	2890	3102	
Lime	3102	3349	
Shale & Lime	3349	3425	
Lime	3425	3612	
Shale	3612	3630	
Shale & Lime	3630	3789	

NOV 9 1990

WHITE & ELLIS DRILLING, INC.