

API NUMBER 15-191-21,324  
 LEASE NAME Stewart # 0000  
 WELL NUMBER #3  
 SPOT LOCATION SE NW SW  
 SEC. 19 TWP. 33 RGE. 3 (E) or (W)  
 COUNTY Sumner  
 Date Well Completed 9/13/81  
 Plugging Commenced 3/18/85  
 Plugging Completed 3/18/85

TYPE OR PRINT  
 NOTICE: Fill out completely  
 and return to Cons. Div.  
 office within 30 days.

LEASE OPERATOR Samson Resources  
 ADDRESS 2 West Second - Tulsa, OK 74103  
 PHONE # (918) 583-1791 OPERATORS LICENSE NO. 5463  
 Character of Well oil  
 (Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Dist #2

Is ACO-1 filed? yes If not, Is well log attached? —

Producing formation Mississippi Depth to top 4183' bottom 4191' T.D. 4590'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

| Formation | Content | From | To | Size             | Put in        | Pulled out   |
|-----------|---------|------|----|------------------|---------------|--------------|
| MPSS      | Oil     | 4183 | 91 | 8 5/8"<br>5 1/2" | 267'<br>4558' | None<br>2240 |
|           |         |      |    |                  |               |              |
|           |         |      |    |                  |               |              |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set.  
Well is plugged up to 3444'. We Duged 50' of Chute and Duged 5 SX Cement. Shot Pipe Line at 22400 Layd Pipe Down Pumped 15 SX Gel and 115 SX Cement Down 8 5/8"

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor B+S Well Service Inc. License No. 6013  
 Address Box 837 Winfield Ks.

STATE OF Kansas COUNTY OF Cowley, ss.

Dale Smith (employee of operator) of APR 15 1985  
 (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) [Signature]  
 (Address) Winfield Ks. 67156



SUBSCRIBED AND SWORN TO before me this 19th day of March, 1985

Wayne C. Leftwich  
 Notary Public

My Commission expires: 2-24-88

W E L L L O G

15-191-21324-0000

WELL NAME: Stewart #3

OPERATOR: Samson Resources

SPUD DATE: 8-26-81

CONTRACTOR: Ramco Drilling Company

COMPLETION DATE: 9-4-81

CASING: 8 5/8, 24# new, set @ 273'  
w/200 sx cmn, 1/2# Flow seal, 3% cc

LOCATION: SE NW SW  
Sec. 19-33S-3w  
Sumner County

---

| <u>FORMATION</u>      | <u>FROM</u> | <u>TO</u> |
|-----------------------|-------------|-----------|
| Surface               | 0           | 273       |
| Sand                  | 273         | 700       |
| Sand                  | 700         | 1220      |
| Sand and Shale        | 1220        | 1450      |
| Shale w/Lime Speck    | 1450        | 1782      |
| Shale and Lime Specks | 1782        | 2096      |
| Shale and Lime        | 2096        | 3319      |
| Lime and Shale        | 3319        | 3835      |
| Shale and Lime        | 3835        | 4115      |
| Mississippi Lime      | 4115        | 4215      |
| Lime and Shale        | 4215        | 4490      |
| Smpson                | 4490        | 4590      |
| RTD                   | 4590        |           |

RECEIVED  
STATE CORPORATION COMMISSION

MAR 9

DAVID W. HILL, DIRECTOR  
Wichita, Kansas

RECEIVED  
STATE CORPORATION COMMISSION

JAN 22 1985