

15-191-00406-0000

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Biting Building  
Wichita, Kansas

WELL PLUGGING RECORD

NORTH

0			

Locate well correctly on above Section Plat

Summer County. Sec. 1 Twp. 31S Rge. (E) 2 (W)  
 Location as "NE/CNW%SW%" or footage from lines C NW SW NW  
 Lease Owner Falcon Seaboard Drilling Company  
 Lease Name Ingram Well No. 1  
 Office Address Pan American Bldg., Tulsa, Oklahoma  
 Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
 Date well completed 10/15 19 57  
 Application for plugging filed 10/15 19 57  
 Application for plugging approved 10/18 19 57  
 Plugging commenced 10/16 19 57  
 Plugging completed 10/16 19 57  
 Reason for abandonment of well or producing formation \_\_\_\_\_

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
 Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eugene Graham  
 Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3800 Feet  
 Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				10-3/4"	540'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Hole was full of mud. Placed HOWCO Plug @ 240 feet, run 15 sacks cement on top of plug. Filled with mud to 40 feet, placed HOWCO plug @ 40 feet. Run 10 sacks cement on top of plug. Welded steel cap on top of surface casing.

RECORDED  
 10-28-57  
 CONF. FILED

Name of Plugging Contractor Company tools.  
 Address \_\_\_\_\_

STATE OF OKLAHOMA COUNTY OF TULSA, ss.  
J. O. BROWN (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) J. O. Brown  
Pan American Building, Tulsa, Oklahoma (Address)

SUBSCRIBED AND SWORN to before me this 24th day of October, 19 57

Dalores Walsh

My commission expires February 8, 1958.

Notary Public.

PLUGGING  
 FILE SEC. L.T. 31 R. 2W  
 BOOK PAGE 54 LINE 12

WELL LOG

COMPANY: Falcon Seaboard Drilling Company

Sec. 1-31S-2W

FARM: Ingram No. 1

Loc. NW SW NW

TOTAL DEPTH: 3,800'

County - Sumner

COMM: 10-2-57. COMP: 10-16-57

CASING

ELEVATION

10-3/4" - 540'

D.F. - 1330'  
Gr. - 1322'

DRILLER'S LOG

Surface Soil, Red Bed & Lime Shells	0	305
Lime & Shale	305	583
Shale & Shells	583	600
Shale & Lime	600	800
Shale & Shells	800	1035
Shale & Lime Shells	1035	1265
Lime & Shale	1265	1417
Shale & Lime Stks.	1417	1560
Shale & Lime	1560	2273
Shale	2273	2775
Shale & Sand	2775	2922
Shale	2922	3100
Lime	3100	3463
Lime & Shale	3463	3785
Lime	3785	3800
Total Depth		3800

RECEIVED  
STATE CORPORATION COMMISSION  
OCT 18 1957  
CONSERVATION DIVISION  
Wichita, Kansas

PLUGGING	
FILE SEC	1 T 31 R 2W
BOOK PAGE	64 LINE 12