

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

Sumner

County. Sec. 1 Twp. 31 Rge. 2 (E) W. (W)

Location as "NE/CNW/SW" or footage from lines NE 1/4 SW 1/4 NW 1/4

Lease Owner J. P. Gaty

Lease Name Ingram Well No. 1

Office Address 11 Cypress Drive, Wichita, Kansas.

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole.

Date well completed January 18, 19 53

Application for plugging filed January 19, 19 53

Application for plugging approved January 19, 19 53

Plugging commenced January 19, 19 53

Plugging completed January 19, 19 53

Reason for abandonment of well or producing formation Dry Hole.

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes.

Name of Conservation Agent who supervised plugging of this well W. G. Buffington

Producing formation Miss. Lime Depth to top 3747 Bottom Total Depth of Well 3826 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8"	390	None.

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled with heavy rotary mud 3826 to 390'
15 Sacks Cement at 390'. Filled with heavy rotary mud to 20'
10 Sacks Cement 20' to 0'

RECEIVED
STATE CORPORATION COMMISSION
JAN 20 1953
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor H. M. Williams,
Address 701 Bitting Building, Wichita, Kansas.


STATE OF Kansas, COUNTY OF Sedgwick, ss.
H. M. Williams (employee of owner) or (owner or operator) of the above-described well,
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *H. M. Williams*
Wichita, Kansas.
(Address)

SUBSCRIBED AND SWORN TO before me this 20th day of January, 19 53.

My commission expires Feb. 2, 1953.

R. P. Downey
Notary Public.



WELL LOG

J. P. Gaty Ingram No. 1.
 Total Depth 3826 R.B.
 Drilling Comm. 1-4-53
 Drilling Comp. 1-18-53
 Drilling Contractor, H. M. Williams

Sec. 1 - 31 - 2 W.
 NEc SW NW.
 Sumner County, Kansas.
 Production - Dry.
 Elevation 1328' R.B.
 Casing:
 8 5/8" 390'

FIGURES INDICATE BOTTOM OF FORMATIONS.

Clay and Sand	205	
Shale & Shells	285	
Shale & Anhydrite	390	
Broken Lime & Shells	525	
Sand, Shale & Shells	750	
Shale & Lime	1030	
Shale, Lime & Red Bed	1140	
Lime	1200	
Lime & Shale	1365	
Soft Lime & Shale	1610	
Shale & Lime	1875	
Shale	1918	
Lime	1948	
Shale & Lime	2122	
Lime	2185	
Lime & Shale	2296	
Lime Shells & Shale	2382	
Shale & Lime	2468	
Sandy Lime & Shale	2592	
Shale & Lime	2771	
Sand - Stalnaker	2877	
Sand & Shale	2892	
Shale & Lime	3080	
Shale & Lime, Broken	3091	
Lime	3281	Top K.C./ Lime 3091
Lime & Shale	3730	
Shale	3747	
Lime	3826	Top Miss. Lime 3747
Total Depth	3826	R.B.

STATE OF KANSAS)
 COUNTY OF SEDGWICK.) SS.

This is to certify that the above is a true and correct copy of the driller's log of the above well.

Subscribed and sworn to before me, a Notary Public, this 20th day of January, 1953.

My commission expires:
 Feb. 2, 1953.

R.P. Comoy
 Notary Public.

RECEIVED
 STATE CORPORATION COMMISSION

JAN 20 1953

CONSERVATION DIVISION
 Wichita, Kansas

