


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Sumner County, Sec. 2 Twp. 32s Rge. 2w E/W
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines
100' E NW NW NW
Lease Owner Hummon Corporation
Lease Name Shore Well No. 1
Office Address 400 one main place Wichita Ks. 67202
Character of Well (Completed as Oil, Gas or Dry Hole) _____



Locate well correctly on above
Section Plot

Gas
Date Well completed 6-15-78 19
Application for plugging filed May 30 1980 19
Application for plugging approved May 30 1980 19
Plugging commenced 6-7-80 19
Plugging completed 6-10-80 19
Reason for abandonment of well or producing formation _____

Depleted
If a producing well is abandoned, date of last production _____ 19

Was permission obtained from the Conservation Division or
its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Carl Barnett
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 1950
Show depth and thickness of all water, oil and gas formations. _____ 1950

OIL, GAS OR WATER RECORDS

CASING RECORD

| FORMATION | CONTENT | FROM | TO | SIZE | PUT IN | PULLED OUT |
|-----------|---------|------|----|-------|--------|------------|
| | | | | 8 5/8 | 235' | none |
| | | | | 4 1/2 | 1941 | 1546 |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Sanded hole to 1900' set 4 sks. cement with bailer
pulled 1546' of 4 1/2" casing set rock bridge at ~~1500~~ 445' and filled
with ready mix cement to base of celler

JUN 29 1980

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Voth Casing Pulling

STATE OF Kansas COUNTY OF Cowley, ss.

Walter Voth (employee of owner) or (owner or operator)

of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Walter Voth

SUBSCRIBED AND SWORN TO before me this 13th day of June, 1980

(Address) _____
Yvonne M. Duncan
Notary Public.

My commission expires June 1, 1981

GABBERT-JONES, INC.
 WICHITA, KANSAS
 DRILLERS' WELL LOG

Shore #1
 100' E of NW-NW-NW Sec 2-32S-2W
 Sumner County Kansas

Commenced: 6-11-78

Completed: 6-15-78

OPERATOR: HUMMON OIL CO.

| Depth | | Formation | Remarks |
|-------|---------|----------------|---|
| From | to | | |
| 0 | 238 | Shale-Shells | Ran 6 jts of 28# 8 5/8" csg set @ 235' Cemented w/200 sks Common 2% Gel 3% CC PD @ 12:15 a.m. 6-12-78 |
| 238 | 270 | Red Rock-Shale | |
| 270 | 775 | Shale | |
| 775 | 980 | Shale-Shells | |
| 980 | 1160 | Shale | |
| 1160 | 1325 | Lime | Ran 58 jts of 10 1/2# 4 1/2" csg set @ 1941' Cemented w/ 75 sks 18% Salt Posmix PD @ 11:30 p.m. 6-15-78 |
| 1325 | 1770 | Shale-Lime | |
| 1770 | 1883 | Lime-Shale | |
| 1883 | 1905 | Sand | |
| 1905 | 1950 | Shale | |
| | 1950 TD | | |

STATE OF KANSAS)
) SS
 COUNTY OF SEDGWICK)

I, the undersigned, being duly sworn on oath, state that the above
 Drillers' Well Log is true and correct to the best of my knowledge and belief and
 according to the records of this office.

GABBERT-JONES, INC.

James S. Sutton II
 JAMES S. SUTTON II

Subscribed and sworn to before me this 20th day of June, 1978.

Elizabeth J. Edwards
 ELIZABETH J. EDWARDS-NOTARY PUBLIC

My Commission expires February 6, 1979.

