

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-101-21,605-0000

LEASE NAME McWhirter

WELL NUMBER 1

990 Ft. from S Section Line

1650 Ft. from E Section Line

SEC. 3 TWP. 19 RGE. 29 ~~X&X~~(W)

COUNTY Lane

Date Well Completed 11-29-91

Plugging Commenced 11-29-91

Plugging Completed 11-29-91

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Anderson Energy, Inc.

ADDRESS 200 E. First - #414, Wichita, KS 67202

PHONE#(316) 265-7929 OPERATORS LICENSE NO. 6484

Character of Well D & A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on November 29, 1991 (date)

by Richard Lacy (KCC District Agent's Name).

Is ACO-1 filed? No If not, Is well log attached? No

Producing Formation _____ Depth to Top _____ Bottom T.D. 4650'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

RECEIVED
STATE CORPORATION COMMISSION
12-6-91
DEC 06 1991

Formation	Content	From	To	Size	Put In	Pulled
				8 5/8"	335'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
Spotted 50 sx. cement at 2180' thru drill pipe. Spotted 10 sx. cement at 40' -
Spotted 80 sx. cement at 1400' thru drill pipe. thru drill pipe.
Spotted 40 sx. cement at 700' thru drill pipe. Spotted 15 sx. cement in rathole
Spotted 50 sx. cement at 360' thru drill pipe.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor White & Ellis Drilling, Inc. License No. 5420

Address P. O. Box 48848, Wichita, KS 67201-8848

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Anderson Energy, Inc.

STATE OF KANSAS COUNTY OF SEDGWICK, ss.

Michael L. Considine (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Michael L. Considine

(Address) P. O. Box 48848
Wichita, KS 67201-8848

SUBSCRIBED AND SWORN TO before me this 3rd day of December, 19 91

My Commission Expires:

CAROLYN J. TJADEN
NOTARY PUBLIC
STATE OF KANSAS
My Appt. Exp. Sept. 5, 1992

Carolyn J. Tjaden
Notary Public

EFFECTIVE DATE: 11-24-91

State of Kansas

101-21,605-0000

FORM MUST BE TYPED

DISTRICT #

NOTICE OF INTENTION TO DRILL

FORM MUST BE SIGNED
ALL BLANKS MUST BE FILLED

SGA? Yes No

Must be approved by the K.C.C. five (5) days prior to commencing well

Expected Spud Date November 15, 1991
month day year

N/2 ^{Spot} SE SW Sec 3 Twp 19 S. Rg 29 East West

OPERATOR: License # 6484
Name: Anderson Energy, Inc.
Address: 200 E. First St., Suite 414
City/State/Zip: Wichita, KS 67202
Contact Person: William L. Anderson
Phone: (316) 265-7929

990 feet from South ~~West~~ line of Section ~~1~~
~~1980~~ feet from East / West line of Section ~~1~~
IS SECTION REGULAR IRREGULAR

(NOTE: Locate well on the Section Plat on Reverse Side)
County: Lane
Lease Name: McWhirter Well #: 1
Field Name: McWhirter

CONTRACTOR: License #: 5420
Name: White & Ellis Drilling, Inc.

Is this a Prorated/Spaced Field? yes no

Target Formation(s): Lansing-KC

Nearest lease or unit boundary: 990'

Ground Surface Elevation: 2819' est. feet MSL

Water well within one-quarter mile: yes no

Public water supply well within one mile: yes no

Depth to bottom of fresh water: 100'

Depth to bottom of usable water: 1370'

Surface Pipe by Alternate: 1 2

Length of Surface Pipe Planned to be set: 200'

Length of Conductor pipe required: N/A

Projected Total Depth: 4650'

Formation at Total Depth: Mississippian

Water Source for Drilling Operations:

.... well farm pond other

DWR Permit #:

Will Cores Be Taken?: yes no

If yes, proposed zone:

Well Drilled For:	Well Class:	Type Equipment:
<input checked="" type="checkbox"/> Oil	<input checked="" type="checkbox"/> Enh Rec	<input checked="" type="checkbox"/> Infield
<input type="checkbox"/> Gas	<input type="checkbox"/> Storage	<input type="checkbox"/> Pool Ext.
<input type="checkbox"/> OUVU	<input type="checkbox"/> Disposal	<input type="checkbox"/> Wildcat
<input type="checkbox"/> Seismic; ... # of Holes	<input type="checkbox"/> Other	<input type="checkbox"/> Cable
<input type="checkbox"/> Other		

If OUVU: old well information as follows:

Operator:

Well Name:

Comp. Date: Old Total Depth

Directional, Deviated or Horizontal wellbore? yes no

If yes, true vertical depth:

Bottom Hole Location:

Exp. 4/30/92

AFFIDAVIT

200' Alt. II Req.

The undersigned hereby affirms that the drilling, completion and eventual plugging of this well will comply with K.S.A. 55-101, et. seq.

It is agreed that the following minimum requirements will be met:

Pusher Judy 605

SPUD DATE 11-19-91 INIT. SM

LENGTH SURFACE PLANNED 200'

RESERVE PIT STATUS- REMOVE FLUID LINED
after salt sect. bbbls. when done bbbls.

RATHOLE AHEAD? Y N SIZE HOLE _____

SURFACE PIPE 8 3/4" @ 335 CONDUCTOR _____

ANHYDRITE T- 2167 B- 2184 ELEVATION _____

TD 4650 FORMATION MISS

RAN PIPE @ _____ DV TOOL _____ ALT II DONE _____
SX _____ Y _____ N _____

Arbuckle Plug @ _____ Ft. W/ _____ SX

Hug./Council @ _____ Ft. W/ _____ SX

Anhydrite Base @ 2180 Ft. W/ 50 SX

1/2 Base Anyh. @ 1400 Ft. W/ 80 SX

1/2, 1/2 Plug @ 700 Ft. W/ 40 SX

Bottom Surface @ 360 Ft. W/ 50 SX

40' Plug @ 360 Ft. W/ 10 SX

RAT HOLE CIRC/W 15 SX MOUSE HOLE W/ _____ SX

WATER WELL _____ SX (Irr. Well _____ Pond _____)
Hauling _____


TECHNICIAN A.L. DATE 11-22-91

TYPE OF CEMENT 60/40 per 6 bags 1/4th Flashed

STARTING TIME 4:00 (AM/PM) DATE 11-29-91

COMPLETION TIME 2:50 (AM/PM) DATE 11-29-91

CEMENT COMPANY Allied



PROPERTY STATE OF KANSAS

DEC 06 1991

15-101-21605-0000

WHITE

ANDELLISDRILLING, Inc.

DRILLERS LOG

OPERATOR: Anderson Energy, Inc., 200 E. First - #414, Wichita, KS 67202

CONTRACTOR: White & Ellis Drilling, Inc. 401 E. Douglas - Suite 500
Wichita, Kansas 67202

Lease Name McWhirter Well No. 1

Sec. 3 T. 19S R. 29W Spot N/2 SE SW

County Lane State Kansas Elev. _____

Casing Record:

Surface: 8 5/8" @ 335' with 180 sx.

Production: _____ @ _____ with _____ sx.

Type Well: D & A Total Depth 4650'

Drilling Commenced 11-20-91 Drilling Completed 11-29-91

Formation	From	To	Tops
Cellar	0	5	Anhydrite 2161
Sand, Shale, Post Rock	5	336	Topeka 3755
Shale	336	790	Topeka/Lansing 3845
Shale & Sand	790	2160	Lansing/KC 4030
Shale	2161	2850	Kansas City 4175
Shale & Lime	2850	3335	Marmaton 4338
Lime & Shale	3335	4650	Marmaton/ Pawnee 4430
			Pawnee/Ft. Scott 4530
			Johnson 4570
			Johnson/Miss 4590
			Miss 4600