

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15 - 101 - 21,178-0000

LEASE NAME Snyders

WELL NUMBER 1-3

990 Ft. from S Section Line

2310 Ft. from E Section Line

SEC. 3 TWP. 19 RGE. 29 (SE) or (W)

COUNTY Lane

Date Well Completed 6-21-85

Plugging Commenced 6-21-85

Plugging Completed 6-21-85

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Rine Exploration & McDonald-Wallace

ADDRESS 300 W. Douglas Suite #645 Wichita, KS 67202

PHONE# (316) 262-5418 OPERATORS LICENSE NO. 5020 & 6390

Character of Well D&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? YES

Which KCC/KDHE Joint Office did you notify? District # 1 Richard Lacey, State Pluggger

is ACO-1 filed? _____ If not, is well log attached? _____

Producing Formation D&A Depth to Top _____ Bottom _____ T.D. 4633'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Surface		0	399	8 5/8	396	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

4633' T.D. 160 Sacks 60-40 Posmix 3% cc 2% Gel
1st Plug @ 2162' w/20 sx Solid Bridge @ 40' w/10 sx
2nd Plug @ 1355' w/80 sx Rat Hole w/10 sx
3rd Plug @ 446' w/40 sx Plug down 4:30 P.M. 6-21-85
(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Blue Goose Drilling Co., Inc License No. 5104


Address P.O. Box 1413 Great Bend, KS 67530

STATE OF KANSAS COUNTY OF BARTON, ss.

Martin E. Miller (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) [Signature]

(Address) Box 1413 Great Bend, KS 67530



7-18-85
FJUI

My Commission Expires: 12-8-87

Helen C. Standley
Notary Public

CARD MUST BE TYPED

State of Kansas
NOTICE OF INTENTION TO DRILL
(see rules on reverse side)

CARD MUST BE SIGNED

Starting Date: 06-17-85
month day year

API Number 15- 101-21,178 ⁻⁰⁰⁰⁰ 2
XXXXXX
NW¹ SW¹ SE¹ Sec. 3 Twp. 19 S. Rge. 29 West

OPERATOR: License # 5020 & 6390
Name Rine Exploration & McDonald-Wallace
Address Suite #645, 300 W. Douglas
City/State/Zip Wichita, KS 67202
Contact Person M. Bradford Rine
Phone 316/262-5418

990 Ft North from Southeast Corner of Section
2310 Ft West from Southeast Corner of Section
(Note: Locate well on Section Plat on reverse side)

CONTRACTOR: License # 5104
Name Blue Goose Drilling, Inc.
City/State Great Bend, KS 67530

Nearest lease or unit boundary line 330 feet.
County Lane
Lease Name Snyders Well# 1-3
Domestic well within 330 feet: yes no
Municipal well within one mile: yes no

Well Drilled For: Well Class: Type Equipment:
 Oil Swd Infield Mod Rotary
 Gas Inj Pool Ext. Air Rotary
 OWWO Expl Wildcat Cable

Depth to Bottom of fresh water 100 feet
Lowest usable water formation Dakota *Cherokee*
Depth to Bottom of usable water 1000 feet
Surface pipe by Alternate: 1 2
Surface pipe to be set 375 feet
Conductor pipe if any required N/A feet
Ground surface elevation 2817 (L&S) feet MSI
This Authorization Expires 12-3-85

If OWWO: old well info as follows:
Operator
Well Name
Comp Date Old Total Depth
Projected Total Depth 4650 feet
Projected Formation at TD Mississippian
Expected Producing Formations Lansing-Kansas City,
Marmaton & Fort Scott

Approved By *6-3-85* The production string will be cemented immediately below the useable water depth.
Partner / Land Operations
Form C-1 4/84

I certify that we will comply with K.S.A. 55-101, et seq., plus eventually plugging hole to K.C.C. specifications.

Date 05/30/85 Signature of Operator or Agent *Wm D. Hess* Title

Set 375' of 8 5/8" on 6/ 85 PCH for KOHE

RECEIVED
STATE CORPORATION COMMISSION
JUL 01 1985
CONSERVATION DIVISION
Wichita, Kansas